



2005 Tri-Service Infrastructure Systems Conference & Exhibition

St. Louis, MO

“Re-Energizing Engineering Excellence”

2-4 August 2005

Agenda

Panel: The Future of Engineering and Construction

- LTG Carl A. Strock, Commander, USACE
- Dr. James Wright, Chief Engineer, NAVFAC

Panel: USACE Engineering and Construction

- Dr. Michael J. O'Connor, Director, R&D

Panel: Navy General Session

- Mr. Steve Geusic, Engineering Criteria & Programs NAVFAC Atlantic

Introduction to Multi-Disciplinary Tracks, by Mr. Gregory W. Hughes

Engineering Circular: Engineering Reliability Guidance for Existing USACE Civil Works Infrastructure, by Mr. David M. Schaaf, PE, LRD Regional Technical Specialist, Navigation Engineering Louisville District

MILCON S&A Account Study, by Mr. J. Joseph Tyler, PE, Chief, Programs Integration Division, Directorate of Military Programs HQUSACE

Financial Justification on Bentley Enterprise License Agreement (ELA)

Track 1

- The Chicago Shoreline Storm Damage Reduction Project, by Andrew Benziger
- Protecting the NJ Coast Using Large Stone Seawalls, by Cameron Chasten
- Cascade: An Integrated Coastal Regional Model for Decision Support and Engineering Design, by Nicholas C. Kraus and Kenneth J. Connell
- Modeling Sediment Transport Along the Upper Texas Coast, by David B. King Jr., Jeffery P. Waters and William R. Curtis
- Sediment Compatibility for Beach Nourishment in North Carolina, by Gregory L. Williams
- Evaluating Beachfill Project Performance in the USACE Philadelphia District, by Monica Chasten and Harry Friebe
- US Army Corps of Engineers' National Coastal Mapping Program, by Jennifer Wozencraft
- Flood Damage Reduction Project Using Structural and Non-Structural Measures, by Stacey Underwood
- Shore Protection Project Performance Improvement Initiative (S3P2I), by Susan Durden
- Hurricane Isabel Post-Storm Assessment, by Jane Jablonski
- US Army Corps of Engineers Response to the Hurricanes of 2004, by Rick McMillen and Daniel R. Haubner
- Increased Bed Erosion Due to Increased Erosion Due to Ice, by Decker B. Hains, John I. Remus, and Leonard J. Zabilansky
- Mississippi Valley Division, by James D. Gutshall
- Impacts to Ice Regime Resulting from Removal of Milltown Dam, Clark Fork River, Montana, by Andrew M. Tuthill and Kathleen D. White, and Lynn A. Daniels
- Carroll Island Micromodel Study: River Miles 273.0-263.0, by Jasen Brown
- Monitoring the Effects of Sedimentation from Mount St. Helens, by Alan Donner, Patrick O'Brien and David Biedenharn
- Watershed Approach to Stream Stability and Benefits Related to the Reduction of Nutrients, by John B. Smith
- A Lake Tap for Water Temperature Control Tower Construction at Cougar Dam, Oregon, by Stephen Schlenker, Nathan Higa and Brad Bird
- San Francisco Bay Mercury TMDL – Implications for Constructed Wetlands, by Herbert Fredrickson, Elly Best and Dave Soballe
- Abandoned Mine Lands: Eastern and Western Perspectives, by Kate White and Kim Mulhern
- Translating the Hydrologic Tower of Babel, by Dan Crawford
- Demonstrating Innovative River Restoration Technologies: Truckee River, Nevada, by Chris Dunn
- System-Wide Water Resource Management – Tools of the Trade

Track 2

- Ecological and Engineering Considerations for Dam Decommissioning, Retrofits, and Reoperations, by Jock Conyngham
- Hydraulic Design of tidegates and other Water Control structures for Ecosystem Restoration projects on the Columbia River estuary, by Patrick S. O'Brien
- Surface Bypass & Removable Spillway Weirs, by Lynn Reese
- Impacts of using a spillway for juvenile fish passage on typical design criteria, by Bob Buchholz
- Howard Hanson Dam: Hydraulic Design of Juvenile Fish Passage Facility in Reservoir with Wide Pool Fluctuation, by Dennis Mekkers and Daniel M. Katz
- Current Research in Fate Current Research in Fate & Transport of Chemical and Biological Contaminants in Water Distribution Systems, by Vincent F. Hock
- Regional Modeling Requirements, by Maged Hussein
- Tools for Wetlands Permit Evaluation: Modeling Groundwater and Surface Water Interaction, by Cary Talbot
- Ecosystem Restoration for Fish and Wildlife Habitat on the UMRS, by Jon Hendrickson
- Missouri River Shallow Water Habitat Creation, by Dan Pridal
- Aquatic Habitat Restoration in the Lower Missouri River, by Chance Bitner
- Transition to an Oracle Based Data System (Corps Water Management System, CWMS), by Joel Asunskis
- RiverGages.com: The Mississippi Valley Division Water Control Website, by Rich Engstrom
- HEC-ResSim 3.0: Enhancements and New Capabilities, by Fauwaz Hanbali
- Hurricane Season 2004 – Not to Be Forgotten, by Jacob Davis
- Re-Evaluation of a Flood Control Project, by Ferris W. Chamberlin
- Helmand Valley Water Management Plan, by Jason Needham
- A New Approach to Water Management Decision Making, by James D. Barton
- Developing Reservoir Operational Plans to Manage Erosion and Sedimentation during Construction – Willamette Temperature
- Control, Cougar Reservoir 2002-2005, by Patrick S. O'Brien
- Improved Water Supply Forecasts for the Kootenay Basin, by Randal T. Wortman
- ResSIM Model Development for Columbia River System, by Arun Mylvahanan
- Prescriptive Reservoir Modeling and the ROPE, by Jason Needham
- Missouri River Basin Water Management, by Larry Murphy

Track 3

- Corps Involvement in FEMA's Map Modernization Program, by Kate White, John Hunter and Mark Flick
- Innovative Approximate Study Method for FEMA Map Moderniation Program , by John Hunter
- Flood Fighting Structures Demonstration and Evaluation Program (FFSD), by Fred Pinkard
- Integrating Climate Dynamics Into Water Resources Planning and Management, by Kate White
- Hydrologic and Hydraulic Contributions to Risk and Uncertainty Propagation Studies, by Robert Moyer
- Uncertainty Analysis: Parameter Estimation, by Jackie P. Hallberg
- Geomorphology Study of the Middle Mississippi River, by Eddie Brauer
- Bank Erosion and Morphology of the Kaskaskia River, by Michael T. Rodgers
- Degradation of the Kansas City Reach of the Missouri River, by Alan Tool
- Sediment Impact Assessment Model (SIAM), by David S. Biedenham and Meg Jonas
- Mississippi River Sedimentation Study, by Basil Arthur
- Sediment Model of Rivers, by Charlie Berger
- East Grand Forks, MN and Grand Forks, ND Local Flood Damage Reduction Project, by Michael Leshner
- Hydrologic and Hydraulic Analyses, by Thomas R. Brown
- Hydrologic and Hydraulic Modeling of the Mccook and Thornton Tunnel and Reservoir Plans, by David Kiel
- Ala Wai Canal Project, by Lynnette F. Schaper
- Missouri River Geospatial Decision Support Framework, by Bryan Baker and Martha Bullock
- Systemic Analysis of the Mississippi & Illinois Rivers Upper Mississippi River Comprehensive Plan, by Dennis L. Stephens

Section 227: National Shoreline Erosion Control Demonstration and Development Program Annual Workshop

- Workshop Objectives
- Section 227: Oil Piers, Ventura County, CA, by Heather Schlosser
- An Evaluation of Performance Measures for Prefabricated Submerged Concrete Breakwaters: Section 227 Cape May Point, New Jersey Demonstration Project, by Donald K Stauble, J.B. Smith and Randall A. Wise
- Bluff Stabilization along Lake Michigan, using Active and Passive Dewatering Techniques, by Rennie Kaunda, Eileen Glynn, Ron Chase, Alan Kehew, Amanda Brotz and Jim Selegan
- Storm Damage at Cape Lookout
- Branchbox Breakwater Design at Pickleweed Trail, Martinez, CA
- Section 227: Miami, FL
- Section 227: Sheldon Marsh Nature Preserve
- Section 227: Seabrook, New Hampshire
- Jefferson County, TX – Low Volume Beach Fill
- Sacred Falls, Oahsacred Falls, Oahu Section 227 Demonstration Project

Track 4

- Fern Ridge LakFern Ridge Lake Hydrologic Aspects of Operation during Failure, by Bruce J Duffe
- A Dam Safety Study Involving Cascading Dam Failures, by Gordon Lance
- Spillway Adequacy Analysis of Rough River Lake Louisville District, by Richard Pruitt
- Water Management in Iraq: Capability and Marsh Restoration, by Fauwaz Hanbali
- Iraq Ministry of Water Resources Capacity Building, by Michael J. Bishop, John W. Hunter, Jeffrey D. Jorgeson, Matthew M. McPherson, Edwin A. Theriot, Jerry W. Webb, Kathleen D. White, and Steven C. Wilhelms

- HEC Support of the CMEP Program, by Mark Jensen
- Geospatial Integration of Hydrology & Hydraulics Tools for Multi-Purpose, Multi-Agency Decision Support, by Timothy Pangburn, Joel Schlagel, Martha Bullock, Michael Smith, and Bryan Baker
- GIS & Surveying to Support FEMA Map Modernization and Example Bridge Report, by Mark Flick
- High Resolution Bathymetry and Fly-Through Visualization, by Paul Clouse
- Using GIS and HEC-RAS for Flood Emergency Plans, by Stephen Stello
- High Resolution Visualizations of Multibeam Data of the Lower Mississippi River, by Tom Tobin and Heath Jones
- System Wide Water Resources Program Unifying Technologies Geospatial Applications, by Andrew J. Bruzewicz
- Raystown Plate Locations
- Hydrologic Engineering Center: HEC-HMS Version 3.0 New Features, by Jeff Harris
- SEEP2D & GMS: Simple Tools for Solving a Variety of Seepage Problems, by Clarissa Hansen, Fred Tracy, Eileen Glynn, Cary Talbot and Earl Edris
- Sediment and Water Quality in HEC-RAS, by Mark Jensen
- Advances to the GSSHA Model, by Aaron Byrd and Cary Talbot
- Watershed Analysis Tool: HEC-WAT Program, by Chris Dunn
- Little Calumet River UnsteadLittle Calumet River Unsteady Flow Model Conversion UNET to HEC-RAS, by Rick D. Ackerson
- Kansas River Basin Model, by Edward Parker
- Design Guidance for Breakup Ice Control Structures, by Andrew M. Tuthill
- Computational Hydraulic Model of the Lower Monumental Dam Forebay, by Richard Stockstill, Charlie Berger, John Hite, Alex Carrillo, and Jane Vaughan
- Use of Regularization as a Method for Watershed Model Calibration, by Brian Skahill
- Demonstration Program Urban Flooding and Channel Restoration in Arid and Semi-Arid Regions (UFDP), by Joan Pope, Jack Davis, Ed Sing, John Warwick, Meg Jonas

Track 5

- Walla Walla District Northwestern Division, by Robert Berger
- Best Practices for Conduits through Embankment Dams, by Chuck R. Cooper
- Design, Construction Design, Construction and Seepage at Prado Dam, by Douglas E. Chitwood
- 2-D Liquefaction Evaluation with Q4Mesh, by David C. Serafini
- Unlined Spillway Erosion Risk Assessment, by Johannes Wibowo, Don Yule, Evelyn Villanueva and Darrel Temple
- Seismic Remediation of the Clemson Upper and Lower Diversion Dams; Evaluation, Conceptual Design and Design, by Lee Wooten and Ben Foreman
- Seismic Remediation of the Clemson Upper and Lower Diversion Dams; Deep Soil Mix Construction, by Lee Wooten and Ben Foreman
- Historical Changes in the State of the Art of Seismic Engineering and Effects of those changes on the Seismic Response Studies of Large Embankment Dams, by Sam Stacy
- Iwakuni Runway Relocation Project, by Vincent R. Donnally
- Internal Erosion & Piping at Fern Ridge Dam, by Jeremy Britton
- Rough River Dam Safety Assurance Project, by Timothy M. O’Leary
- Seepage Collection & Control Systems: The Devil is in the Details , by John W. France
- Dewey Dam Seismic Assessment, by Greg Yankey
- Seismic Stability Evaluation for Ute Dam, New Mexico, by John W. France
- An Overview of Criteria Used by Various Organizations for Assessment and Seismic Remediation of Earth Dams, by Jeffrey S. Dingrando
- A Review of Corps of Engineers Levee Seepage Practices and Proposed Future Changes, by George Sills
- Ground-Penetrating Radar Applications for the Assessment of Pavements, by Lulu Edwards and Don R. Alexander
- Peru Road Upgrade Project, by Michael P. Wielputz
- Slope Stability Evaluation of the Baldhill Dam Right Abutment, by Neil T. Schwanz
- Design and Construction of Anchored Bulkheads with Synthetic Sheet Piles Seabrook, New Hampshire, by Siamac Vaghar and Francis Fung
- Characterization of Soft Claya Case Study at Craney Island, by Aaron L. Zdinak
- Dispersive ClayDispersive Clays – Experience andHistory of the NRCS (Formerly SCS), by Danny McCook
- Post-Tensioning Institute, by Michael McCray
- Demonstration Program Urban Flooding and Channel Restoration in Arid and Semi-Arid Regions (UFDP), by Joan Pope, Jack Davis, Ed Sing, John Warwick, Meg Jonas

Track 6

- State of the Art in Grouting: Dams on Solution Susceptible or Fractured Rock Foundations, by Arthur H. Walz
- Specialty Drilling, Testing, and Grouting Techniques for Remediation of Embankment Dams, by Douglas M. Heenan
- Composite Cut-Offs for Dams, by Dr. Donald A. Bruce and Trent L. Dreese
- State of the Art in Grout Mixes, by James A. Davies
- State of the Art in Computer Monitoring and Analysis of Grouting, by Trent L. Dreese and David B. Wilson
- Quantitatively Engineered Grout Curtains, by David B. Wilson and Trent L. Dreese
- Grout Curtains at Arkabutla Dam: Outlet Monolith Joints and Cracks using Chemical Grout, Arkabutla Lake, MS, by Dale A. Goss
- Chicago Underflow Plan – CUP: McCook Reservoir Test Grout Program, by Joseph A. Kissane
- Clearwater Dam: Sinkhole Repair Foundation Investigation and Grouting Project, by Mark Harris
- Update on the Investigation of the Effects of Boring Sample Size (3” vs 5”) on Measured Cohesion in Soft Clays, by Richard Pinner and Chad M. Rachel
- Soil-Bentonite Cutoff Wall Through Free-Product at Indiana Harbor CDF, by Joe Schulenberg and John Breslin
- Soil-Bentonite Cutoff Wall Through Dense Alluvium with Boulders into Bedrock, McCook Reservoir, by William A. Rochford
- Small Project, Big Stability Problem the Block Church Road Experience, by Jonathan E. Kolber
- Determination of Foundation Rock Properties Beneath Folsom Dam, by Michael K. Sharp, José L. Llopis and Enrique E. Matheu
- Waterbury Dam Mitigation, by Bethany Bearmore
- Armor Stone Durability in the Great Lakes Environment, by Joseph A. Kissane
- Mill Creek - An Urban Flood Control Challenge, by Monica B. Greenwell
- Next Stop, The Twilight Zone, by Troy S. O’Neal
- Limitations in the Back Analysis of Shear Strength from Failures, by Rick Deschamps and Greg Yankey
- Reconstruction of Deteriorated Concrete Lock Walls After Blasting and Other Demolition Removal Techniques, by Stephen G. O’Connor

- Flood Fighting Structures Demonstration and Evaluation Program (FFSD), by George Sills
- Innovative Design Concepts Incorporated into a Landfill Closure and Reuse Design Portsmouth Naval Shipyard, Kittery, Maine, by Dave Ray and Kevin Pavlik
- Laboratory Testing of Flood Fighting Structures, by Johannes L. Wibowo, Donald L. Ward and Perry A. Taylor
- Bluff Stabilization Along Lake Michigan, Using Active and Passive Dewatering Techniques, Allegan Co. Michigan, by Rennie Kaunda, Eileen Glynn, Ron Chase, Alan Kehew and Jim Selegean

Track 7

- Case History: Multiple Axial Statnamic Tests on a Drilled Shaft Embedded in Shale, by Paul J. Axtell, J. Erik Loehr, Daniel L. Jones
- The Sliding Failure of Austin Dam Pennsylvania - Revisited, by Brian H. Greene
- M3 –Modeling, Monitoring and Managing: A Comprehensive Approach to Controlling Ground Movements for Protection of Existing Structures and Facilities, by Francis D. Leathers and Michael P. Walker
- Time-Dependent Reliability Modeling for Use in Major Rehabilitation of Embankment Dams and Foundation, by Robert C. Patev
- Lateral Pile Load Test Results Within a Soft Cohesive Foundation, by Richard J. Varuso
- Engineering Geology Challenge Engineering Geology Challenges During Design and Construction of the Marmet Lock Project, by Ron Adams and Mike Nield
- Mill Creek Deep Tunnel Geologic Conditions and Potential Impacts on Design/Construction, by Kenneth E. Henn III
- McAlpine Lock Replacement Instrumentation: Design, Construction, Monitoring, and Interpretation, by Troy S. O’Neal
- Geosynthetics and Construction of the Second Powerhouse Corner Collector Surface Flow Bypass Project, Bonneville Lock and Dam Project, Oregon and Washington, by Art Fong
- McAlpine Lock Replacement Project Foundation Characteristics and Excavation, by Kenneth E. Henn III
- Structural and Geotechnical Issues Impacting The Dalles Spillwall Construction and Bay 1 Erosion Repair, by Jeffrey M. Ament
- Rock Anchor Design and Construction: The Dalles Dam Spillwalls, by Kristie M. Hartfeil
- The Future of the Discrete Element Method in Infrastructure Analysis, by Raju Kala, Johannes L. Wibowo and John F. Peters
- Sensitive Infrastructure Sites - Sonic Drilling Offers Quality Control and Non-Destructive Advantages to Geotechnical Construction Drilling, by John P. Davis

Track 8

- Evaluation of The Use of LithiumEvaluation of The Use of Lithium Compounds in Controlling ASR in Concrete Pavement, by Mike Kelly
- Roller Compacted Concrete for McAlpine Lock Replacement, by David E. Kiefer
- Soil-Cement for Stream Bank Stabilization, by Wayne Adaska
- Using Cement to Reclaim Asphalt Pavements, by David R. Luhr
- Valley Park 100-Yr Flood Protection Project: Use of ‘Engineered Fill’ in the Item IV-B Levee Core, by Patrick J. Conroy
- Bluestone Dam: AAR –A Case Study, by Greg Yankey
- USDA Forest Service: Unpaved Road Stabilization with Chlorides, by Michael R. Mitchell
- Use of Ultra-Fine Amorphous Colloidal Silica to Produce a High-Density, High-Strength Grout, by Brian H. Green
- Modular Gabion Systems, by George Ragazzo
- Addressing Cold Regions Issues in Pavement Engineering, by Edel R. Cortez and Lynette Barna
- Geology of New York Harbor: Geological and Geophysical Methods of Characterizing the Stratigraphy for Dredging Contracts, by Ben Baker, Kristen Van Horn and Marty Goff
- Rubblization of Airfield Concrete Pavements, by Eileen M. Vélez-Vega
- US Army Airfield Pavement Assessment Program, by Haley Parsons, Lulu Edwards, Eileen Velez-Vega and Chad Gartrell
- Critical State for Probabilistic Analysis of Levee Underseepage, by Douglas Crum,
- Curing Practices for Modern Concrete Production, by Toy Poole
- AAR at Carters Dam: Different Approaches, by James Sanders
- Concrete Damage at Carters Dam, by Toy Poole
- Damaging Interactions Among Concrete Materials, by Toy Poole
- Economic Effects on Construction of Uncertainty in Test Methods, by Toy Poole
- Trends in Concrete Materials Specifications, by Toy Poole
- Spall and Intermediate-Sized Repairs for PCC Pavements, by Reed Freeman and Travis Mann
- Acceptance Criteria Acceptance Criteria for Unbonded Aggregate Road Surfacing Materials, by Reed Freeman, Toy Poole, Joe Tom and Dale Goss
- Effective Partnering to Overcome an Interruption In the Supply of Portland Cement During Construction at Marmet Lock and Dam, by Billy D. Neeley, Toy S. Poole and Anthony A. Bombich

Track 10

- Marmet Lock &Dam: Automated Instrumentation Assessment, Summer/Fall 2004, by Jeff Rakes and Ron Adams
- Success Dam Seismic Remediation

Track 9

- Fern Ridge Dam, Oregon: Seepage and Piping Concerns (Internal Erosion)

Track 11

- Canton Dam Spillway Stability: Is a Test Anchor Program Necessary?, by Randy Mead
- Dynamic Testing and Numerical Correlation Studies for Folsom Dam, by Ziyad Duron, Enrique E. Matheu, Vincent P. Chiarito, Michael K. Sharp and Rick L. Poeppelman

- Status of Portfolio Risk Assessment, by Eric Halpin
- Mississinewa Dam Foundation Rehabilitation, by Jeff Schaefer
- Wolf Creek Dam Seepage Major Rehabilitation Evaluation, by Michael F. Zoccola
- Bluestone Dam DSA Anchor Challenges, by Michael McCray
- Clearwater Dam Major Rehab Project, by Bobby Van Cleave
- Design, Construction and Seepage at Prado Dam, by Douglas E. Chitwood
- Seven Oaks Dam: Outlet Tunnel Invert Damage, by Robert Kwan
- An Overview of An Overview of the Dam Safety ProgramManagement Tools (DSPMT), by Tommy Schmidt

Track 12

- Greenup L&D Miter Gate Repair and Instrumentation, by Joseph Padula, Bruce Barker and Doug Kish
- Marmet Locks and Dam Lock Replacement Project, by Jeffrey S. Maynard,
- Status of HSS Inspections in The Portland District, by Travis Adams
- Kansas City District: Perry Lake Project Gate Repair, by Marvin Parks
- Mel Price – Auxiliary Lock Downstream Miter Gate Repair, by Thomas J. Quigley, Brian K. Kleber and Thomas R. Ruf
- J.T. Myers Lock Improvements Project Infrastructure Conference, by David Schaaf and Greg Werncke
- J.T. Myers Dam Major Rehab, by David Schaaf, Greg Werncke and Randy James
- Greenup L&D, by Rodney Cremeans
- McAlpine Lock Replacement Project, by Kathy Feger
- Roller Compacted Concrete Placement at McAlpine Lock, by Larry Dalton
- Kentucky Lock Addition Downstream Middle Wall Monolith Design, by Scott A. Wheeler
- London Locks and Dam Major Rehabilitation Project, by David P. Sullivan
- Replacing Existing Lock 4: Innovative Designs for Charleroi Lock, by Lisa R. Pierce, Dave A. Stensby and Steve R. Stoltz
- Olmsted L&D, Dam In-the-wet Construction, by Byron McClellan, Dale Berner and Kenneth Burg
- Olmsted Floating Approach Walls, by Terry Sullivan
- John Day Navigation Lock Monolith Repair, by Matthew D. Hanson
- Inner Harbor Navigation Canal (IHNC) Lock Replacement, by Mark Gonski
- Comite River Diversion Project, by Christopher Dunn
- Waterline Support Failure: A Case Study, by Angela DeSoto Duncan
- Public Appeal of Major Civil Projects: The Good, the Bad and the Ugly, by Kevin Holden and Kirk Sunderman
- Chickamauga Lock and Dam Lock Addition Cofferdam Height Optimization Study, by Leon A. Schieber
- Des Moines Riverwalk, by Thomas D. Heinold

Track 13

- Folsom Dam Evaluation of Stilling Basin Performance for Uplift Loading for Historic Flows and Modification of Folsom Dam
- Stilling Basin for Hydrodynamic Loading, by Rick L. Poeppelman, Yunjing (Vicky) Zhang, and Peter J. Hradilek
- Seismic Stress Analysis of Folsom Dam, by Enrique E. Matheu
- Barge Impact Analysis for Rigid Lock Walls ETL 1110-2-563, by John D. Clarkson and Robert C. Patev
- Belleville Locks & Dam Barge Accident on 6 Jan 05, by John Clarkson
- Portugues Dam Project Update, by Alberto Gonzalez, Jim Mangold and Dave Dollar
- Portugues Dam: RCC Materials Investigation, by Jim Hinds
- Nonlinear Incremental Thermal Stress Strain Analysis Portugues Dam, by David Dollar, Ahmed Nisar, Paul Jacob and Charles Logie
- Seismic Isolation of Mission-Critical Infrastructure to Resist Earthquake Ground Shaking or Explosion Effects, by Harold O. Sprague, Andrew Whitaker and Michael Constantino
- Obermeyer Gated Spillway S381, by Michael Rannie
- Design of High Pressure Vertical Steel Gates Chicago Land Underflow Plan McCook Reservoir, by Henry W. Stewart, Hassan Tondravi, Lue Tekola,
- Development of Design Criteria for the Rio Puerto Nuevo Contract 2D/2E Channel Walls, by Janna Tanner, David Shiver, and Daniel Russell
- Indianapolis NorthIndianapolis North Phase 3A Warfleigh Section
- Design of Concrete Lined Tunnels in Rock CUP McCook Reservoir Distribution Tunnels Contract, by David Force

Track 14

- GSA Progressive Collapse Design Guidelines Applied to Concrete Moment-Resisting Frame Buildings, by David N. Bilow and Mahmoud E. Kamara,
- UFC 4-023-02 Retrofit of Existing Buildings to Resist Explosive Effects, by Jim Caulder
- Summit Bridge Fatigue Study, by Jim Chu
- Quality Assurance for Seismic Resisting Systems, by John Connor
- Seismic Requirements for Arch, Mech, and Elec. Components, by John Connor
- SBEDS - (Single degree of freedom Blast Effects Design Spreadsheets), by Dale Nebuda,
- Design of Buildings to Resist Progressive Collapse UFC 4-023-03, by Bernie Deneke,
- Fatigue and Fracture Assessment, by Jesse Stuart
- Unified Facilities Criteria: Seismic Design for Buildings, by Jack Hayes
- Evaluation and Repair Of Blast Damaged Reinforced Concrete Beams, by MAJ John L. Hudson
- Building an In-house Bridge Inspection Program
- United Facilities CriteriUnited Facilities Criteria Masonry Design for Buildings, by Tom Wright
- USACE Homeland Security Portal, by Michael Pace
- Databse Tools for Civil Works Projects

- Standard Procedure for Fatigue Evaluation of Bridges, by Phil Sauser
- Consolidation of Structural Criteria for Military Construction, by Steven Sweeney
- Cathodic Protectionfor the South Power Plant Reinforcing Steel, Diego Garcia, BIOT, by Thomas Tehada and Miki Funahashi

Track 15

- Engineering Analysis of Airfield Lighting System Lightning Protection, by Dr. Vladimir A. Rakov and Dr. Martin A. Uman
- Dr. Martin A. Uman
- Charleston AFB Airfield Lighting Vault
- UNIFIED FACILITIES CRITERIA (UFC) UFC 3-530-01 Design: Interior, Exterior Lighting and Controls, by Nancy Clanton and Richard Cofer
- Electronic Keycard Access Locks, by Fred A Crum
- Unified Facilities Criteria (UFC) 3-560-02, Electrical Safety, by John Peltz and Eddie Davis
- Electronic Security SystemElectronic Security Systems Process Overview
- Lightning Protection Standards
- Electrical Military Workshop
- Information Technology Systems Criteria, by Fred Skroban and John Peltz
- Electrical Military Workshop
- Electrical Infrastructure in Iraq- Restore Iraqi Electricity, by Joseph Swiniarski

Track 16

- BACnet® Technology Update, by Dave Schwenk
- The Infrastructur Conference 2005, by Steven M. Carter Sr. and Mitch Duke
- Design Consideration for the Prvention of Mold, by K. Quinn Hart
- COMMISSIONING, by Jim Snyder
- New Building Commissioning , by Gary Bauer
- Ventilation and IAQ TheNew ASHRAE Std 62.1, by Davor Novosel
- Basic Design Considerations for Geothermal Heat Pump Systems, by Gary Phetteplace
- Packaged Central Plants
- Effective Use Of Evaporative Cooling For Industrial And Institutional/Office Facilities, by Leon E. Shapiro
- Seismic Protection For Mechanical Equipment
- Non Hazardous Chemical Treatments for Heating and Cooling Systems, by Vincent F. Hock and Susan A. Drozd
- Trane Government Systems & Services
- LONWORKS Technology Update, by Dave Schwenk
- Implementation of Lon-Based Specifications by Will White and Chris Newman

Track 17

- Utility System Security and Fort Future, by Vicki Van Blaricum, Tom Bozada, Tim Perkins, and Vince Hock
- Festus/Crystal City Levee and Pump Station
- Chicago Underflow Plan McCook Reservoir (CUP) Construction of Distribution Tunnel and Pumps Installation
- Technological Advances in Lock Control Systems, by Andy Schimpf and Mike Maher
- Corps of Engineers in Iraq Rebuilding Electrical Infrastructure, by Hugh Lowe
- Red River of the North at East Grand Forks, MN & Grand Forks, ND: Flood Control Project – Armada of Pump Stations Protect Both Cities, by Timothy Paulus
- Lessons Learned for Axial/Mixed Flow Propeller Pumps, by Mark A. Robertson
- Creek Automated Gate Considerations, by Mark A. Robertson
- HydroAMP: Hydropower Asset Management, by Lori Rux
- Acoustic Leak Detection for Water Distribution Systems, by Sean Morefield, Vincent F. Hock and John Carlyle
- Remote Operation System, Kaskaskia Dam Design, Certification, & Accreditation, by Shane M. Nieukirk
- Lock Gate Replacement System, by Shaun A. Sipe and Will Smith

Track 20

- “Re-Energizing Medical Facility Excellence”, by COL Rick Bond
- Rebuilding and Renovating The Pentagon , by Brian T. Dziekonski,
- Resident Management System
- Design-Build and Army Military Construction, by Mark Grammer
- Defense Acquisition Workforce Improvements Act - Update, by Mark Grammer
- Construction Management @ Risk: Incentive Price Revision – Successive Targets, by Christine Hendzlik
- Construction Reserve Matrix, by Christine Hendzlik
- Award contingent on several factors..., by Christine Hendzlik
- 52.216-17 Incentive Price Revision--Successive Targets (Oct 1997) - Alt I (Apr 1984), by Christine Hendzlik
- Preconstruction Services, by Christine Hendzlik
- Proposal Evaluation Factors, by Christine Hendzlik
- MILCON Transformation in Support of Army Transformation, by Claude Matsui
- Construction Practices in Russia, by Lance T. Lawton

- Partnering as a Best Practice, by Ray Dupont
- USACE Tsunami Reconstruction for USAID, by Andy Constantaras

Track 21

- Dredging Worldwide, by Don Carmen
- SpecsIntact Editor, by Steven Freitas
- SpecsIntact Explorer, by Steven Freitas
- American River Watershed Project, by Steven Freitas
- Unified Facilities Guide Specifications (UFGS) Conversion To MasterFormat 2004, by Carl Kersten
- Unified Facilities Guide Specifications (UFGS) Status and Direction , by Jim Quinn

Workshops

- Design of Buildings to Resist Progressive Collapse UFC 4-023-03, by Bernie Deneke
- Security Engineering and at Unified Facility Criteria (UFC), by Bernie Deneke, Richard Cofer, John Lynch and Rudy Perkey
- Packaged Central Plants, by Trey Austin



2005 Tri-Service Infrastructure Systems Conference & Exhibition

*"Re-Energizing Engineering
Excellence"*

ON-SITE AGENDA

*The America's Center
St. Louis Convention Center
St. Louis, MO
August 2-4, 2005
Event # 5150*



AGENDA

Monday, August 1, 2005

- 8:00 AM-9:00 PM Exhibit Move-In
- 12 Noon-5:00 PM Registration

Tuesday, August 2, 2005

- 7:00 AM-8:00 AM Registration and Continental Breakfast
- 8:00 AM-8:15 AM Welcome and Introduction
Ferrara Theatre
- 8:15 AM-9:00 AM The Future of Engineering and Construction Panel
Ferrara Theatre
Moderator:
Mr. Don Basham, Chief, Engineering & Construction, USACE
Panelists:
LTG Carl A. Strock, Commander, USACE
Dr. James Wright, Chief Engineer NAVFAC
- 9:00 AM-9:45 AM Keynote Address
Ferrara Theater
The Lord of the Things: The Future of Infrastructure Technologies
Mr. Paul Doherty, AIA, Managing Director, General Land Corporation
- 9:45 AM-10:15 AM Break
- 10:15 AM-11:15 AM USACE Engineering and Construction Panel
Ferrara Theatre
Moderator:
Mr. Don Basham, Chief, Engineering & Construction, USACE
Panelists:
MG Donald T. Riley, Director, Civil Works, USACE
BG Bo M. Temple, Director, Military Programs, USACE
Dr. Michael J. O'Connor, Director, R&D
- 10:15 AM-11:15 AM Navy General Session
Room 225
- 11:00 AM - 7:00 PM Exhibits Open
- 11:15 AM-1:00 PM Lunch in Exhibit Hall (on your own)
- 11:15 AM-1:00 PM Women's Career Lunch Session (Bring your lunch from Exhibit Hall)
Washington G
Moderator:
Ms. Demi Syriopoulou, HQ USACE
Opening Remarks:
LTG Carl A. Strock, Commander, USACE
Presentations & Discussion:
Dwight Beranek, Kristine Allaman, Donald Basham, HQ USACE
- 1:00 PM-1:55 PM Introduction to Multi-Disciplinary Tracks
Ferrara Theatre

- | | |
|-----------------------|--|
| Track 1:
Room 230 | Acquisition Strategies for Civil Works
<i>Walt Norko</i> |
| Track 2:
Room 231 | Risk and Reliability Engineering
<i>Anjana Chudgar</i>
<i>David Schaaf</i> |
| Track 3:
Room 232 | Portfolio Risk Assessment
<i>Eric Halpin</i> |
| Track 4:
Room 240 | Hydrology, Hydraulics and Coastal Engineering
Support for USACE
<i>Jerry Webb</i>
<i>Darryl Davis</i> |
| Track 5:
Room 241 | Civil Works R&D Forum
<i>Joan Pope</i> |
| Track 6:
Room 242 | Civil Works Security Engineering
<i>Joe Hartman</i>
<i>Bryan Cisar</i> |
| Track 7:
Room 226 | Building Information Model Applications
<i>Brian Huston</i>
<i>Daniel Hawk</i> |
| Track 8:
Room 220 | Design Build for Military Projects
<i>Mark Grammer</i> |
| Track 9:
Room 221 | Army Transformation/Global Posture Initiative/
Force Modernization
<i>Al Young</i>
<i>Claude Matsui</i> |
| Track 10:
Room 222 | Force Protection - Army Access Control Points
<i>John Trout</i> |
| Track 11:
Room 227 | Cost Engineering Forum on Government Estimates
vs. Actual Costs
<i>Ray Lynn</i> <i>Jack Shelton</i> <i>Kim Callan</i>
<i>Miguel Jumilla</i> <i>Ami Ghosh</i> <i>Joe Bonaparte</i> |
| Track 12:
Room 228 | Engineering & Construction Information Technology
<i>MK Miles</i> |
| Track 13:
Room 223 | Sustainable Design
<i>Harry Goradia</i> |
| Track 14:
Room 224 | ACASS/CCASS/CPARS
<i>Ed Marceau</i>
<i>Marilyn Nedell</i> |
| Track 15:
Room 229 | Whole Building Design Guide
<i>Earle Kennett</i> |

Tuesday, August 2, 2005

2:50 PM-3:30 PM	Break in Exhibit Hall
3:30 PM-4:20 PM	2 nd Round of Multi-Disciplinary Sessions
4:30 PM-5:20 PM	3 rd Round of Multi-Disciplinary Sessions
5:30 PM-7:00 PM	Ice Breaker Reception in Exhibit Hall

Wednesday, August 3, 2005

7:00 AM-8:00 AM	Registration and Continental Breakfast
8:00 AM-9:30 AM	Concurrent Sessions (Please Refer to Concurrent Session Schedule on the Following Pages)
9:00 AM	Exhibit Hall Opens
9:30 AM-10:30 AM	Break in Exhibit Hall
10:30 AM-12:00 Noon	Concurrent Sessions (Please Refer to Concurrent Session Schedule on the Following Pages)
12:00 Noon-1:30 PM	Lunch in Exhibit Hall
1:30 PM-3:00 PM	Concurrent Sessions (Please Refer to Concurrent Session Schedule on the Following Pages)
3:00 PM-4:00 PM	Break in Exhibit Hall
4:00 PM-5:30 PM	Concurrent Sessions
5:00 PM	Exhibit Hall Closes

Thursday, August 4, 2005

7:00 AM-8:00 AM	Registration and Continental Breakfast
8:00 AM-9:30 AM	Concurrent Sessions (Please Refer to Concurrent Session Schedule on Following Pages)
9:30 AM-10:30 AM	Break in Exhibit Hall (Last Chance to view Exhibits)
10:30 AM-12:00 Noon	Concurrent Sessions (Please Refer to Concurrent Session Schedule on Following Pages)
12:00 Noon-1:30 PM	Lunch (On your own)
12:00 Noon-6:00 PM	Exhibits Move-Out
1:30 PM-3:00 PM	Concurrent Sessions (Please Refer to Concurrent Session Schedule on Following Pages)
3:00 PM-3:30 PM	Break
3:30 PM-5:00 PM	Concurrent Sessions (Please Refer to Concurrent Session Schedule on following pages)

Wednesday, August 3, 2005 Concurrent Sessions

HH&C Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 220	TRACK 1 Coastal Structures	Protecting the NI Coast using large stone seawalls	Chicago shoreline storm damage reduction project	Risk and reliability in coastal structure design	TRACK 1 Coastal Regional Manangement Session 1B	Cascade: An integrated regional model for decision support	Upper Texas coast sediment transport modeling & sediment budgets Carolina
	Session 1A	Cameron Chasten	Andrew Bezinger	Jeffrey Malby	Nicholas Kraus	David King	Gregory Williams
Room 221	TRACK 2 Ecological Engineering & Design	Ecological and engineering considerations for dam decommissioning, retrofits and operations	Hydraulic design of tidegates and other water control structures for ecosystem restoration on the Columbia Estuary	Innovative Integration of engineering and biological tools aids hydraulic structure design for restoring T&E fish	TRACK 2 Ecological Engineering & Design	Innovative hydraulic structure design at Lower Granite Dam: design that saves water and salmon	Impacts of using a spillway for juvenile fish passage on reservoir with wide range of pool elevation - Hanson Dam
	Session 2A	Jock Conyngham	Patrick O'Brien	Andrew Goodwin	Lynn Reese	Robert Buchholz	Dennis Mekkers
Room 222	TRACK 3 Modeling	Corps involvement in the FEMA map modernization program	Innovative approximate study method for FEMA map modernization program	Flood fight structures demonstration evaluation program	TRACK 3 Modeling	Integrating climate dynamics into water resources planning and management	Risk and uncertainty in flood damage reduction studies
	Session 3A	Kate White	John Hunter	Fred Pinkard	Kate White	Rob Moyer	Jackie Hallberg
Room 223	TRACK 4 H&H Aspects of Dam Safety	Hydrologic aspects of operating in failure mode: Fern Lake	Dam safety study with cascading failures	Rough river spillway capacity	TRACK 4 International/Military H&H	Capability restoration and historic marsh restoration effort for Iraq MoWR	USACE support of CMEP in 2004
	Session 4A	Bruce Duffe	Gordon Lance	Richard Pruitt	Fauwaz Hanbali	Steven Wilhelms	Mark Jensen

12 Noon

Lunch in Exhibit Hall

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	4:00 PM	4:30 PM	5:00 PM
Room 220	TRACK 1 Coastal Sediments	Evaluating beachfill project performance in the NAP	USACE's regional coastal mapping program	US Naval Academy flood damage reduction project using structural and non-structural measures	TRACK 1 Shore Protection Projects	Hurricane Isabel effects on communities	Repair of the shore protection projects adversely affected by the hurricanes of 2004
	Session 1C	Monica Chasten	Jennifer Wozencraft	Stacey Underwood	Session 1D	Jane Jablonski	Rick McMillen
Room 221	TRACK 2 Modeling Ecological Restoration/Systems Assessment Session 2C	Regional modeling requirements for ecosystem restoration	Tools for wetlands permit evaluation: Modeling groundwater and surface water distribution systems	Current research in fate and transport of chemical and biological contaminants in water distribution systems	TRACK 2 Ecosystem Habitat Restoration	Aquatic habitat restoration in the lower Missouri River	Missouri River restoration: shallow water habitat creation
	Session 2C	Maged Hussein	Cary Talbot	Mark Ginsberg	Session 2D	Chance Bittner	Daniel Pridal
Room 222	TRACK 3 River Morphology	Geomorphology study of the Mississippi river	Bank erosion and morphology of the Kaskaskia river	Sediment movement at Kansas City from water years 1920 to 2004	TRACK 3 Modeling River Sedimentation	Sediment impact assessment model (SIAM) MS River, Cairo to Gulf	Sediment modeling of rivers
	Session 3C	Edward Brauer	Michael Rodgers	Alan Tool	Session 3D	David Biedenbarn	Basil Arthur
Room 223	TRACK 4 GIS and Surveying	GIS tools available now to support HHC	High resolution bathymetry and fly-through visualization	GIS & surveying to support national FEMA	TRACK 4 GIS and Surveying	Update flood emergency plans with GIS and HEC-RAS	High resolution visualizations of multibeam data: lower Mississippi River
	Session 4C	Timothy Pangburn	Paul Clouse	Mark Flick	Session 4D	Stephen Stello	Thomas Tobin
							Andrew Bruzewicz

Break in Exhibit Hall

Wednesday, August 3, 2005 Concurrent Sessions

Geotechnical Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
TRACK 5	Levee lowering for the Lewis & Clark bi-centennial celebration <i>Robert Berger</i>	Conduits through embankment dams - best practices for design, construction, problem id and evaluation, inspection, maintenance, renovation & repair <i>Dave Pezza</i>	Design, construction and seepage at Prado Dam, CA <i>Douglas Chitwood</i>		2-D liquefaction evaluation with q4MESH <i>David Serafini</i>	Unlined spillway erosion risk assessment <i>Johannes Wibowo</i>	Seismic remediation of the Clemson upper and lower diversion dams: evaluation, conceptual design and design (P1) <i>Ben Foreman</i>
Session 5A							
TRACK 6	USACE dams on solution susceptible or highly fractured rock foundations <i>Art Walz</i>	Special drilling and grouting techniques for remedial work in embankment dams <i>Doug Heenan</i>	Composite grouting & cutoff wall solutions <i>Donald Bruce</i>				
Session 6A							
TRACK 7	Case history: multiple axial static test on a drilled shaft embedded in shale <i>Paul Axtell</i>	Austin Dam, Pennsylvania: the sliding failure of a concrete gravity dam revisited <i>Brian Greene</i>	M ³ (Modeling, Monitoring and Manufacturing) - a comprehensive approach to controlling ground movements for protecting existing structures and facilities <i>Michael Walker</i>				
Session 7A							
TRACK 8	Evaluation of the use of lithium nitrate in controlling alkali-silica reactivity in an existing concrete pavement <i>Mike Kelly</i>	Use of self-consolidating concrete in the installation of bulbhead slots - Lessons learned in the use of this innovative concrete material <i>Darrell Morey</i>	Roller compacted concrete for McAlpine lock walls <i>David Kiefer</i>				
Session 8A							
Session 5B							
TRACK 6							
Session 6B							
TRACK 7							
Session 7B							
TRACK 8							
Session 8B							

Break in Exhibit Hall

12 Noon

Lunch in Exhibit Hall

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	4:00 PM	4:30 PM	5:00 PM
TRACK 5	Seismic remediation of the Clemson upper and lower diversion dams: deep soil mix construction <i>Ben Foreman</i>	Historical changes in the state-of-the-art of seismic engineering & effects of those changes on the seismic response studies of large embankment dams <i>Samuel Stacy</i>	New Iwakuni runway <i>Vincent Donnelly</i>		Internal erosion and piping at Fern Ridge dam: Problems and solutions <i>Jeremy Britton, Ph.D.</i>	Rough river dam safety assurance project <i>Timothy O'Leary</i>	Seepage collection and control systems: The devil is in the details <i>John France</i>
Session 5C							
TRACK 6	Grout curtains at Arkabutla Dam outlet monolith joints using chemical grout to seal joints, Arkabutla, MS <i>Dale Goss</i>	Results from a large-scale grout test program, Chicago underflow plan (CUP) McCook Reservoir <i>Joseph Kissane</i>	Clearwater Dam - foundation drilling and grouting for repair of sinkholes <i>Mark Harris</i>		Update on the investigation of the effects of boring sample size (3' vs 5'') on measured cohesion in soft clays <i>Richard Pinner</i>	Soil-bentonite cutoff wall through dense alluvium with boulders into bedrock, McCook Reservoir <i>Joseph Schulenberg</i>	Soil-bentonite cutoff wall through dense alluvium with boulders into bedrock, McCook Reservoir <i>William Rochford</i>
Session 6C							
TRACK 7	Engineering geology during design and construction of the Marmet lock project <i>Michael Nield</i>	Mill Creek deep tunnel - Geological affects on proposed structures and construction techniques <i>Tres Henn</i>	Earth pressure loads behind the new McAlpine Lock replacement project <i>Troy O'Neal</i>		Geosynthetics and construction of the Bonneville lock and dam second powerhouse corner collector surface flow bypass project <i>Art Fong</i>	McAlpine lock replacement - foundation characteristics and excavation <i>Kenneth Henn</i>	Addressing cold regions issues in pavement engineering <i>Lynette Barna</i>
Session 7C							
TRACK 8	What to do if your dam is expanding: a case study <i>Greg Yankey</i>	Unpaved road stabilization with chlorides <i>Michael Mitchell</i>	Use of ultra-fine amorphous colloidal silica to produce a high-density, high-strength rock-matching grout for instrumentation grouting <i>Brian Green</i>		Innovative techniques in the Gabion system <i>George Ragazzo</i>	Addressing cold regions issues in pavement engineering <i>Ben Baker</i>	Geology of New York Harbor - geological and geophysical methods of characterizing the stratigraphy for dredging contracts <i>Ben Baker</i>
Session 8C							

Break in Exhibit Hall

Wednesday, August 3, 2005 Concurrent Sessions

Structural Engineering Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 240	TRACK 12 Civil Works Structural	Recent changes to Corps guidance on steel hydraulic structures	Crack repairs and instrumentation of Greenup Lock miter gate	Recent hydraulic steel structures findings in the Portland district	TRACK 12 Civil Works Structural	Perry Lake gate repair	Mel Price auxiliary lock gate repair (Continued)
	Session 12A	<i>Joe Padula</i>	<i>Doug Kish</i>	<i>Travis Adams</i>	Session 12B	<i>Marvin Parks</i>	<i>Andrew Schimpf</i>
Room 241	TRACK 13 Civil Works Structural	Folsom Dam evaluation of stilling basin performance for uplift loading for historic flows	Rehabilitation of Folsom Dam stilling basin	Seismic stability evaluation of Folsom Dam	TRACK 13 Civil Works Structural	Seismic stress analysis of Folsom Dam	Barge impact guidance for rigid lock walls, ETL 110-2-563 and probabilistic barge impact analysis
	Session 13A	<i>Rick Poeppelman</i>	<i>Rick Poeppelman</i>	<i>Enrique Matheu</i>	Session 13B	<i>Enrique Matheu</i>	<i>John Clarkson</i>
Room 242	TRACK 14 Bridges/ Buildings	The USACE bridge management system	Standard procedures for fatigue evaluation of bridges	Fatigue and fracture assessment of Jesse Stuart Highway Bridge	TRACK 14 Bridges/ Buildings	Building an in-house bridge inspection program	Fatigue analysis of Summit bridge
	Session 14A	<i>Phil Sausser</i>	<i>Phil Sausser</i>	<i>John Jaeger</i>	Session 14B	<i>Jennifer Laning</i>	<i>Jim Chu</i>
							<i>Steve Sweeney</i>

Break in Exhibit Hall

12 Noon

Lunch in Exhibit Hall

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	4:00 PM	4:30 PM	5:00 PM
Room 240	TRACK 12 Civil Works Structural	Overview of John T. Myers locks improvements project	John T. Myers rehabilitation study	Ohio River Greenup Lock extension	TRACK 12 Civil Works Structural	McAlpine lock replacement project, project summary and status of construction	Results of Roller Compacted concrete placement at the McAlpine lock replacement project
	Session 12C	<i>Greg Werncke</i>	<i>Greg Werncke</i>	<i>Rodney Cremeans</i>	Session 12D	<i>Kathleen Feger</i>	<i>Scott Wheeler</i>
Room 241	TRACK 13 Civil Works Structural	Portugues Dam, Ponce, Puerto Rico project update	Portugues Dam, Ponce, Puerto Rico, RCC design and testing program	Portugues Dam, Ponce, Puerto Rico, Thermal analysis of hydration and subsequent cooling of RCC	TRACK 13 Civil Works Structural	Miter gate anchorage design	Obermeyer gated spillway project - S381 high pressure steel gates
	Session 13C	<i>Jim Mangold</i>	<i>Jim Hinds</i>	<i>Ahmed Nisar</i>	Session 13D	<i>Andy Harkness</i>	<i>Luelsaged Tekola</i>
Room 242	TRACK 14 Bridges/ Buildings	Unified facilities criteria seismic design for buildings	Seismic requirements for architectural, mechanical and electrical components	Quality assurance for seismic resisting systems	TRACK 14 Bridges/ Buildings	Unified facilities criteria masonry structural design for buildings	Catholic protection of building reinforcing steel web portal (in Diego Garcia)
	Session 14C	<i>Jack Hayes</i>	<i>John Connor</i>	<i>John Connor</i>	Session 14D	<i>Tom Wright</i>	<i>Thomas Tehada</i>
							<i>Mike Pace</i>

Break in Exhibit Hall

Wednesday, August 3, 2005 Concurrent Sessions

Dam Safety Track & Construction Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 224	TRACK 10 Dam Safety	Tuttle Creek warning and alert systems <i>Bill Empson</i>	Lessons from the dam failure warning system exercise - Tuttle Creek <i>Bill Empson</i>	Tuttle Creek ground modification treatability program <i>Bill Empson</i>	TRACK 10 Dam Safety	Dam safety analysis of Cannelton Dam <i>Terry Sullivan</i>	John Martin Dam, CO - Dam safety structural upgrades <i>George Diwald</i>
Room 225	Session 10A	<i>Bill Empson</i>	<i>Bill Empson</i>	<i>Bill Empson</i>	Session 10B	<i>Terry Sullivan</i>	<i>George Diwald</i>
	TRACK 11 Dam Safety	Canton lake spillway stabilization project: IS a test anchor program NECESSARY? <i>Randy Mead</i>	Dynamic testing and numerical correlation studies for Folsom dam <i>Ziyad Duron</i>	Status of portfolio risk assessment <i>Eric Halpin</i>	TRACK 11 Dam Safety	Mississinewa Dam remediation <i>Jeff Schaefer</i>	Wolf creek seepage history <i>Michael Zoccola</i>
Room 230	Session 11A	<i>Randy Mead</i>	<i>Ziyad Duron</i>	<i>Eric Halpin</i>	Session 11B	<i>Jeff Schaefer</i>	<i>Michael Zoccola</i>
	TRACK 19 Construction	RMS Update <i>Haskell Barker</i>	RMS Update (Continued) <i>Haskell Barker</i>	Updated CQM for Contractors Course <i>Walt Norko</i>	TRACK 19 Construction	Lessons learned on major construction projects <i>Jim Cox</i>	Update on safety issues - Safety manual 385-1-1 (continued) <i>Charles Ray Waits</i>
	Session 19A	<i>Haskell Barker</i>	<i>Haskell Barker</i>	<i>Walt Norko</i>	Session 19B	<i>Jim Cox</i>	<i>Charles Ray Waits</i>
Room 231	TRACK 20 Construction	Construction methods in Russia <i>Lance Lawton</i>	Construction methods in Russia (Continued) <i>Lance Lawton</i>	Renovating the Pentagon using Design/Build delivery <i>Brian Dziekonski</i>	TRACK 20 Construction	Completion of the Olmsted approach walls (Continued) <i>Dale Miller</i>	Completion of the Olmsted approach walls (Continued) <i>Dale Miller</i>
	Session 20A	<i>Lance Lawton</i>	<i>Lance Lawton</i>	<i>Brian Dziekonski</i>	Session 20B	<i>Dale Miller</i>	<i>Christopher Prinslow</i>

12 Noon

Lunch in Exhibit Hall

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	4:00 PM	4:30 PM	5:00 PM
Room 224	TRACK 10 Dam Safety	Project specific risk analysis - Success Dam <i>Ronn Ross</i>	Dam safety lessons learned, Winter storm 2005, Muskingum & Scioto Basins <i>Charles Barry</i>	Dam security and Dams Government Coordinating Council <i>Roy Braden</i>	TRACK 10 Dam Safety	Prompton Dam hydrologic deficiency and spillway modification <i>Troy Cosgrove</i>	"Well, that's water over the dam" - Rough River spillway adequacy design overturning protection <i>Fares Abdo</i>
Room 225	Session 10C	<i>Ronn Ross</i>	<i>Charles Barry</i>	<i>Roy Braden</i>	Session 10D	<i>Troy Cosgrove</i>	<i>Richard Pruitt</i>
	TRACK 11 Dam Safety	Clearwater Dam major rehabilitation <i>Bobby Van Cleave</i>	Success dam seismic dam safety modification <i>Norbert Suter</i>	Problems on the Santa Ana River - Prado Dam <i>Douglas Chitwood</i>	TRACK 11 Dam Safety	Problems on the Santa Ana River - Seven Oaks Dam <i>Robert Kwan</i>	Dam safety program management tools <i>Tommy Schmidt</i>
Room 230	Session 11C	<i>Bobby Van Cleave</i>	<i>Norbert Suter</i>	<i>Douglas Chitwood</i>	Session 11D	<i>Robert Kwan</i>	<i>Tommy Schmidt</i>
	TRACK 19 Construction	3D Modeling and impact on constructability <i>Gary Cough</i>	3D Modeling and impact on constructability (Continued) <i>Gary Cough</i>	Construction in Iraq & Afghanistan <i>Walt Norko</i>	TRACK 19 Construction	Air Force streamlining Design/Build <i>Joel Hoffman</i>	Air Force streamlining Design/Build (Continued) Sustainable design requirements & construction implementation <i>Harry Gioradia</i>
Room 231	Session 19C	<i>Gary Cough</i>	<i>Gary Cough</i>	<i>Walt Norko</i>	Session 19D	<i>Joel Hoffman</i>	<i>Joel Hoffman</i>
	TRACK 20 Construction	Tsunami reconstruction <i>Andy Constantaras</i>	Tsunami reconstruction (Continued) <i>Andy Constantaras</i>	Military construction transformation in support of Army transformation <i>Sally Parsons</i>	TRACK 20 Construction	MEDCOM Construction Issues <i>Rick Bond</i>	MEDCOM Construction Issues (Continued) <i>Rick Bond</i>
	Session 20C	<i>Andy Constantaras</i>	<i>Andy Constantaras</i>	<i>Sally Parsons</i>	Session 20D	<i>Rick Bond</i>	<i>Rick Bond</i>

Break in Exhibit Hall

Wednesday, August 3, 2005 Concurrent Sessions

Electrical & Mechanical Engineering Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room A	TRACK 15 Military Electrical	Tri-Service Electrical Criteria Overview - (Continued)	Tri-Service Electrical Criteria Overview - (Continued)	Tri-Service Panel	TRACK 15 Military Electrical	Interior/Exterior and security lighting criteria	Information technology systems criteria (Continued)
Room B	Session 15A	<i>Tri-Service Panel</i>	<i>Tri-Service Panel</i>	<i>Tri-Service Panel</i>	Session 15B	<i>Tri-Service Panel</i>	<i>Tri-Service Panel</i>
Room D	TRACK 16 Military Mechanical	Building Commissioning	HVAC Commissioning	Ventilation and indoor air quality	TRACK 16 Military Mechanical	Ventilation and indoor air quality (Continued)	Refrigerant implications for HVAC specifications, selection, and o&m - now and future (Continued)
	Session 16A	<i>Dale Herron</i>	<i>Dale Herron</i>	<i>Davor Novosel</i>	Session 16B	<i>Davor Novosel</i>	<i>Mike Thompson</i>
	TRACK 17 Military Mechanical/ Electrical	Sustainable design update			TRACK 17 Military Mechanical/ Electrical	Utility systems security and fort future	Acoustic leak detection for utilities distribution systems (Continued)
	Session 17A	<i>Harry Goradia</i>			Session 17B	<i>Vicki L. Van Blaricum</i>	<i>Sean Morefield</i>
Room E	TRACK 18 Civil Mechanical	Emsworth Dam vertical lift gate hoist replacement	Hydraulic drive for Braddock Dam	John Day navigation lock upstream lift gate wire rope failure	TRACK 18 Civil Mechanical	Overhead bulkhead at Olmstead Lock	Mechanical design issues during construction of McAlpine Lock
	Session 18A	<i>John Nites</i>	<i>Janine Krempa</i>	<i>Ronald Wridge</i>	Session 18B	<i>Rick Schultz</i>	<i>Brenden McKinley</i>
							<i>Richard Nichols</i>

Break in Exhibit Hall

12 Noon

Lunch in Exhibit Hall

	2:00 PM	2:30 PM	3:00 PM	3:30 PM	4:00 PM	4:30 PM	5:00 PM
Room A	TRACK 15 Military Electrical	Mass notification system	Mass notification system (Continued)	Electronic card access locks	TRACK 15 Military Electrical	Lightning protection standards	Lightning and surge protection (Continued)
Room B	Session 15C	<i>Tri-Service Panel</i>	<i>Tri-Service Panel</i>	<i>Fred Crum</i>	Session 15D	<i>Richard Bouchard</i>	<i>Tri-Service Panel</i>
	TRACK 16 Military Mechanical	Basic design considerations for geothermal heat pump systems	Basic design considerations for geothermal heat pump systems (Continued)	Pentagon renovation	TRACK 16 Military Electrical	Effective use of evaporative cooling for industrial and institutional/office facilities (Continued)	Non-hazardous chemical treatments for heating and cooling systems
Room D	Session 16C	<i>Gary Phetteplace</i>	<i>Gary Phetteplace</i>	<i>Mitch Duke</i>	Session 16D	<i>Leon Shapiro</i>	<i>Vincent Hock</i>
	TRACK 17 Civil Mechanical/ Electrical	Hydropower asset management partnership (hydroAMP)	New gas fueled/diesel fueled turbine powered electrical generating station in Iraq	The construction of distribution tunnels and pump installation for the metropolitan Chicago sewer systems	TRACK 17 Civil Mechanical/ Electrical	The Festus/Crystal City levee and pump station project	Technological advances in lock control systems
	Session 17C	<i>Lori Rux</i>	<i>Lester Lowe</i>	<i>Ernesto Go</i>	Session 17D	<i>Stephen Farkas</i>	<i>Shane Nieuirk</i>
Room E	TRACK 18 Civil Mechanical	New coating products for civil works structures	New guide specification for procurement of turbine oils	Synchronous condensing with large Kaplan turbine - A case study	TRACK 18 Civil Mechanical	Acquifer storage and recovery (ASR) system	Storm water pumps
	Session 18C	<i>Al Bettelman</i>	<i>John Micetic</i>	<i>Brian Moentenich</i>	Session 18D	<i>Gerald Deloach</i>	<i>James Jamieson</i>
							<i>James Sadler</i>
							<i>Andy Schimpf</i>

Break in Exhibit Hall

Thursday, August 4, 2005 Concurrent Sessions

HH&C Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 220	TRACK 1 Sedimentation & New Concepts Session 1E <i>Andrew Tuthill</i>	Ice jams, contaminated sediment and structures Clark Fork River, MT <i>John Hains</i>	Monitoring the Mississippi River using GPS coordinated video <i>James Gutshall</i>	Break in Exhibit Hall			
Room 221	TRACK 2 Water Management <i>Fauwaz Hanbali</i>	Enhancements and new capabilities of HEC-ResSim 3.0	Accessing real time Mississippi Valley water level data <i>Rich Engstrom</i>				
Room 222	Session 2E <i>Red River of the north flood protection project</i> <i>Thomas Brown</i>	Transition to Oracle based data system <i>Joel Asunskis</i>	McCook and Thornton tunnel and reservoir modeling <i>David Kiel</i>				
Room 223	Session 2E <i>Hydrologic models supported by ERDC</i> <i>Michael Leshner</i>	HEC-HMS Version 3.0 new features <i>Jeff Harris</i>	SEEP2D & GMS: Simple tools for solving a variety of seepage problems <i>Clarissa Hansen</i>				
	Session 4E <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Robert Wallace</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>				
	Session 1G <i>Developing reservoir operation plans to manage erosion</i> <i>Herb Fredrickson</i>	New approaches to water management decision making <i>James Barton</i>	Improved water supply forecasts for Kootenay basin using principal components regression <i>Randal Wortman</i>				
	Session 2G <i>Little Calumet River unsteady flow model conversion</i> <i>William Curtis</i>	Kansas City River basin model <i>William Curtis</i>	Design guidance for breakup ice control <i>William Curtis</i>				
	Session 3G <i>HEC-ResSim 3.0</i> <i>William Curtis</i>	HEC-HMS Version 3.0 new features <i>James Barton</i>	SEEP2D & GMS: Simple tools for solving a variety of seepage problems <i>Clarissa Hansen</i>				
	Session 4G <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Robert Wallace</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>				

12 Noon

Lunch

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	3:30 PM	4:00 PM	4:30 PM
Room 220	TRACK 1 Water Quality Management <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Herb Fredrickson</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>	Break			
Room 221	TRACK 2 Water Management <i>Developing reservoir operation plans to manage erosion</i> <i>Herb Fredrickson</i>	New approaches to water management decision making <i>James Barton</i>	Improved water supply forecasts for Kootenay basin using principal components regression <i>Randal Wortman</i>				
Room 222	Session 2G <i>Little Calumet River unsteady flow model conversion</i> <i>William Curtis</i>	Kansas City River basin model <i>William Curtis</i>	Design guidance for breakup ice control <i>William Curtis</i>				
Room 223	Session 3G <i>HEC-ResSim 3.0</i> <i>William Curtis</i>	HEC-HMS Version 3.0 new features <i>James Barton</i>	SEEP2D & GMS: Simple tools for solving a variety of seepage problems <i>Clarissa Hansen</i>				
	Session 4G <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Robert Wallace</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>				
	Session 1G <i>Developing reservoir operation plans to manage erosion</i> <i>Herb Fredrickson</i>	New approaches to water management decision making <i>James Barton</i>	Improved water supply forecasts for Kootenay basin using principal components regression <i>Randal Wortman</i>				
	Session 2G <i>Little Calumet River unsteady flow model conversion</i> <i>William Curtis</i>	Kansas City River basin model <i>William Curtis</i>	Design guidance for breakup ice control <i>William Curtis</i>				
	Session 3G <i>HEC-ResSim 3.0</i> <i>William Curtis</i>	HEC-HMS Version 3.0 new features <i>James Barton</i>	SEEP2D & GMS: Simple tools for solving a variety of seepage problems <i>Clarissa Hansen</i>				
	Session 4G <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Robert Wallace</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>				

Lunch

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	3:30 PM	4:00 PM	4:30 PM
Room 220	TRACK 1 Water Quality Management <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Herb Fredrickson</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>	Break			
Room 221	TRACK 2 Water Management <i>Developing reservoir operation plans to manage erosion</i> <i>Herb Fredrickson</i>	New approaches to water management decision making <i>James Barton</i>	Improved water supply forecasts for Kootenay basin using principal components regression <i>Randal Wortman</i>				
Room 222	Session 2G <i>Little Calumet River unsteady flow model conversion</i> <i>William Curtis</i>	Kansas City River basin model <i>William Curtis</i>	Design guidance for breakup ice control <i>William Curtis</i>				
Room 223	Session 3G <i>HEC-ResSim 3.0</i> <i>William Curtis</i>	HEC-HMS Version 3.0 new features <i>James Barton</i>	SEEP2D & GMS: Simple tools for solving a variety of seepage problems <i>Clarissa Hansen</i>				
	Session 4G <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Robert Wallace</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>				
	Session 1G <i>Developing reservoir operation plans to manage erosion</i> <i>Herb Fredrickson</i>	New approaches to water management decision making <i>James Barton</i>	Improved water supply forecasts for Kootenay basin using principal components regression <i>Randal Wortman</i>				
	Session 2G <i>Little Calumet River unsteady flow model conversion</i> <i>William Curtis</i>	Kansas City River basin model <i>William Curtis</i>	Design guidance for breakup ice control <i>William Curtis</i>				
	Session 3G <i>HEC-ResSim 3.0</i> <i>William Curtis</i>	HEC-HMS Version 3.0 new features <i>James Barton</i>	SEEP2D & GMS: Simple tools for solving a variety of seepage problems <i>Clarissa Hansen</i>				
	Session 4G <i>San Francisco Bay Mercury TMDL- Implications for constructed wetlands</i> <i>Robert Wallace</i>	Abandoned mine land: Eastern and Western perspectives <i>Kate White</i>	A lake tap for temperature control tower construction at Cougar Dam <i>Steve Schlenker</i>				

Thursday, August 4, 2005 Concurrent Sessions

Geotechnical Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 226	TRACK 5 Dynamic deformation analyses Dewey Dam Huntington District Corps of Engineers Session 5E Greg Yankey Small geotechnical project, big stability problem - The Block Church Road experience	John France Seismic stability evaluation for Ute Dam, NM Jose Llopis Geophysical investigation of foundation conditions beneath Folsom Dam	Sean Carter An overview of criteria used by various organizations for assessments and seismic remediation of earth dams Bethany Bearmore Bioengineering slope stabilization techniques coupled with traditional engineering applications - The result a stable slope	Break in Exhibit Hall			
Room 227	Session 6E Jonathan Kolber The geotechnical and structural issues impacting the Dalles spillway construction	Kristie Harfheil The Dalles spillway engineering and design	Kristie Harfheil US Army airfield pavement assessment program	Raju Kala Critical state for probabilistic analysis of levee underseepage	Session 5F George Sills Shoreline armor stone quality issues	Lulu Edwards USACE seepage berm design applications for the assessment of airfield pavements	Michael Wielputz Challenges of the Fernando Belaudre Terry road upgrade Campanilla to Pizana - Peru road project
Room 228	Session 7E Kristie Harfheil Rubblization of airfield concrete pavement	Kristie Harfheil Rubblization of airfield concrete pavement	Haley Parsons US Army airfield pavement assessment program	Douglas Crum Critical state for probabilistic analysis of levee underseepage	Session 6F Joseph Kissane Evaluating the portable falling weight deflectometer as a low-cost technique for post-evaluation of success dam control tower on low volume payments	Monica Greenwell Soil structure interaction effects in the seismic evaluation of success dam control tower	Troy O'Neal Olmsted locks and Dam project geotechnical/construction issues
Room 229	Session 8E Eileen Velez-Vega	Haley Parsons	Douglas Crum	Session 7F Maureen Kestler Curing practices for modern concrete construction	Michael Sharp AAR at Carters Dam, a different approach	James Sanders Concrete damage at Carters Dam, GA	Toy Poole Concrete damage at Carters Dam, GA

12 Noon

Lunch

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	3:30 PM	4:00 PM	4:30 PM
Room 226	TRACK 5 Slope stability evaluation of the Baldhill Dam right abutment Session 5G Neil Schwanz Perils in back analysis failures	Richard Varuso Lateral pile load test results within a soft cohesive foundation	Siamac Vaghar Design and construction of anchored bulbheads for river diversion, Seabrook, NH	Session 5H Aaron Zdinak Innovative design concepts incorporated into a landfill closure and reuse design	Danny McCook 50 years of NRSC experience with engineering problems caused by dispersive clays	Danny McCook 50 years of NRSC experience with engineering problems caused by dispersive clays	Michael McCray Changes in the post-tensioning institutes new (4th Ed. 2004) -Recommendations for prestressed rock and soil anchors
Room 227	Session 6G Greg Yankey Geotechnical instrumentation and foundation re-evaluation of John Day lock and Dam, Columbia River, Oregon-Washington	Steve O'Connor Reconstruction of deteriorated lock walls concrete after blasting and other demolition removal techniques	George Sills Flood fighting structures demonstrations and evaluation program	Session 6H Dave Ray Sensitive infrastructure sites and structures - Sonic drilling offers quality control and non-destructive advantages to geotechnical construction drilling	Johannes Wibowo Subgrade failure criteria according to soil type and moisture condition	Johannes Wibowo Subgrade failure criteria according to soil type and moisture condition	Eileen Glynn Bluff stabilization along Lake Michigan using active and passive dewatering techniques
Room 228	Session 7G David Scofield Damaging interactions among concrete materials	John Rice Economic effects on construction of uncertainty in test methods	John France Major issues in materials specifications	Session 7H John Davis Spall and intermediate-sized repairs for PCC pavements	Edel Cortez Acceptance criteria for unbonded aggregate road surfacing materials	Edel Cortez Acceptance criteria for unbonded aggregate road surfacing materials	Robert Jolisian Effective partnering to overcome an interruption in the supply of Portland cement during construction of Marmet lock and Dam
Room 229	Session 8G Toy Poole	Toy Poole	Toy Poole	Session 8H Reed Freeman	Reed Freeman	Reed Freeman	Billy Nealey

Break

Thursday, August 4, 2005 Concurrent Sessions

Geotechnical, Specifications, Electrical & Mechanical Engineering & Construction Tracks

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 225	TRACK 9 Geotechnical	Seepage Committee Meeting (Continued)	Seepage Committee Meeting (Continued)		TRACK 9 Geotechnical	GMCoP Forum (Continued)	GMCoP Forum (Continued)
Room 232	Session 9E	<i>GROUP DISCUSSION</i>	<i>GROUP DISCUSSION</i>	<i>GROUP DISCUSSION</i>	Session 9F	<i>GROUP DISCUSSION</i>	<i>GROUP DISCUSSION</i>
Room A	TRACK 21 Specifications	SpecIniaact-Demonstration of the SI explorer, publishing to PDF and Word	SpecIniaact - Demonstration of the SI editor, UMRL and reference wizard	UFGS status and direction	TRACK 21 Specifications	Project specifications for the upper tier Folsom outlet works modifications	UFGS dredging
Room B	Session 21E	<i>Patricia Robinson</i>	<i>Patricia Robinson</i>	<i>Jim Quinn</i>	Session 21F	<i>Carl Kersten</i>	<i>Don Carmen</i>
Room D	TRACK 15 Military Electrical	Electronic Security (Continued)	Electronic Security (Continued)	AIRFIELD lightning protection & grounding and lighting	TRACK 15 Military Electrical	Electrical safety and are flash UFC (Continued)	Electrical infrastructure in Iraq - Restore Iraqi electricity
Room 230	Session 17E	<i>Mark Robertson</i>	<i>Timothy Paulus</i>	<i>Sara Benier</i>	Session 15F	<i>Tri-Service Panel</i>	<i>Joseph Swiniarski</i>
Room 231	TRACK 19 Construction	NAVFAAC Construction scheduling	NAVFAAC Construction scheduling (Continued)	ACASS/CASS - CPARS	TRACK 16 Military Mechanical	Prefabricated Chiller Plants	Seismic for ME systems the prevention of mold
Room 225	Session 19E	<i>Glenn Saito</i>	<i>Glenn Saito</i>	<i>Ed Marceau</i>	Session 16F	<i>Trey Austin</i>	<i>Quinn Hart</i>
Room 231	TRACK 20 Construction	Update on DAWIA and Facilities Engineering (Continued)	Update on DAWIA and Facilities Engineering (Continued)	Partnering as a best practice	TRACK 17 Civil Mechanical	Lock gate replacement system (Continued)	Automated closure gate design for Duck creek flood control
Room 231	Session 20E	<i>Mark Grammer</i>	<i>Mark Grammer</i>	<i>Ray DuPont</i>	Session 17F	<i>Will Smith</i>	<i>Mark Robertson</i>
Room 231	Session 20F	<i>Harry Jones</i>	<i>Don Basham</i>	<i>Don Basham</i>	TRACK 19 Construction	Self-consolidating concrete (Continued)	Self-consolidating concrete (Continued)
Room 231	Session 19F	<i>Beatrix Kerhoff</i>	<i>Beatrix Kerhoff</i>	<i>Beatrix Kerhoff</i>	Session 20G	<i>Harry Jones</i>	<i>Don Basham</i>
Room 231	Session 20G	<i>Harry Jones</i>	<i>Don Basham</i>	<i>Don Basham</i>	Session 20H	<i>Harry Jones</i>	<i>Don Basham</i>

Break in Exhibit Hall

Lunch

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	3:30 PM	4:00 PM	4:30 PM
Room 225	TRACK 9 Geotechnical	Seismic Manual (Continued)	Seismic Manual (Continued)	Seismic Manual (Continued)			
Room 225	Session 9G	<i>GROUP DISCUSSION</i>	<i>GROUP DISCUSSION</i>	<i>GROUP DISCUSSION</i>			

Thursday, August 4, 2005 Concurrent Sessions

Dam Safety Track & Structural Engineering Track

	8:00 AM	8:30 AM	9:00 AM	9:30 AM	10:30 AM	11:00 AM	11:30 AM
Room 224	TRACK 10 Dam Safety	Seepage and stability, final evaluation for reservoir pool raising project, Terminus Dam, Kaweah River, CA <i>Michael Rambotham</i>	Initial filling plan, Terminus dam spillway enlargement, Terminus Dam, Kaweah River, CA <i>Michael Rambotham</i>	Hydrologic aspects of operating in a "failure mode" - Fern Ridge Lake, OR <i>Bruce Duffe</i>	TRACK 10 Dam Safety	A dam safety study involving cascading dam failures <i>Gordon Lance</i>	The relationship of seismic velocity to the erodibility index <i>Joseph Topi</i>
Room 240	Session 10E	<i>Michael Rambotham</i>	<i>Michael Rambotham</i>	<i>Bruce Duffe</i>	Session 10F	<i>Gordon Lance</i>	<i>Joseph Topi</i>
Room 241	TRACK 12 Civil Works Structural	London lock and dam, West Virginia major rehabilitation project <i>David Sullivan</i>	Replacing existing lock 4-Innovative designs for Charletoi lock <i>Steveb Stoltz</i>	Use of non-linear incremental structural analysis in the design of the Charletoi lock <i>Randy James</i>	TRACK 12 Civil Works Structural	Olmsted dam in-the-wet construction methods <i>Terry Sullivan</i>	John Day lock monolith repair <i>Mathew Hanson</i>
Room 242	Session 13E	<i>Jan Plachta</i>	<i>Robert Reed</i>	<i>Jeremy Nichols</i>	Session 13F	<i>Jan Plachta</i>	<i>Gene Hoard</i>
	TRACK 14 Bridges/ Buildings	Urban search & rescue program overview <i>Tom Niedernhofer</i>	Evaluation and repair of blast damaged reinforced concrete beams <i>John Hudson</i>	Single degree of freedom blast effects spreadsheets <i>Dale Nebuda</i>	TRACK 14 Bridges/ Buildings	UFC 4-023-02 Structural design to resist explosive effects for existing buildings <i>Brian Crowder</i>	U.S. general services administrative progressive collapse design guidelines applied to concrete moment-resisting frame buildings <i>David Billow</i>

12 Noon

Break in Exhibit Hall

Lunch

	1:30 PM	2:00 PM	2:30 PM	3:00 PM	3:30 PM	4:00 PM	4:30 PM
Room 224	TRACK 10 Dam Safety	Dam safety instrumentation data management utilizing WinIDP to aid data collection and evaluation <i>Travis Tutka</i>	Automated instrumentation assessments at Marmet lock & Dam <i>Ronald Rakes</i>	Potential failure mode analysis of Eau Galle Dam <i>David Rydeen</i>	TRACK 10 Dam Safety	Dam safety officers panel - The Good - The Bad <i>Bruce Murray</i>	Dam safety officers panel - The Ugly <i>Bruce Murray</i>
Room 240	Session 12G	<i>Mark Gonski</i>	<i>Christopher Dunn</i>	<i>Angela DeSoto Duncan</i>	Session 12H	<i>Kevin Holden</i>	<i>Thomas Heinold</i>
	TRACK 12 Civil Works Structural	Inner Harbor navigation canal and lock structure <i>Travis Tutka</i>	Design features and challenges of the Comite River diversion project <i>Ronald Rakes</i>	Waterline support failure on the Harvey canal: A case study <i>Angela DeSoto Duncan</i>	TRACK 12 Civil Works Structural	Public appeal of major civil projects- The good, the bad and the ugly <i>Bruce Murray</i>	Chickamauga lock and Dam height optimization study using Monte Carlo simulation <i>Bruce Murray</i>

Break

		1:30 PM		2:00 PM		2:30 PM		3:00 PM		3:30 PM		4:00 PM		4:30 PM	
Room 241	Workshop 1 DoD Security Engineering	Security planning & minimum standards	Curt Betts	National Electrical Code 2005 Changes	Security planning & minimum standards (Continued)	Curt Betts	National Electrical Code 2005 Changes (Continued)	Security planning & minimum standards (Continued)	Workshop 1 DoD Security Engineering	Security design manuals	(Continued)	Security design manuals (Continued)			
Room 231	Workshop 2 Electrical Workshop	Design and application of packaged central cooling plants	Mark McNamara	National Electrical Code 2005 Changes	Design and application of packaged central cooling plants (Continued)	Mark McNamara	National Electrical Code 2005 Changes (Continued)	Security design manuals (Continued)	Session 1B	National Electrical Code 2005 Changes (Continued)	Bernie Deneke	National Electrical Code 2005 Changes (Continued)	Bernie Deneke	National Electrical Code 2005 Changes (Continued)	Bernie Deneke
Room 242	Workshop 3 Mechanical Engineering	Design and application of packaged central cooling plants	Mark McNamara	National Electrical Code 2005 Changes	Design and application of packaged central cooling plants (Continued)	Mark McNamara	National Electrical Code 2005 Changes (Continued)	Security design manuals (Continued)	Session 2A	National Electrical Code 2005 Changes (Continued)	Mark McNamara	National Electrical Code 2005 Changes (Continued)	Mark McNamara	Mark McNamara	Mark McNamara
Room 230	Workshop 4 Construction	Construction Community of Practice Forum	The Trane Company	Construction Community of Practice Forum (Continued)	Construction Community of Practice Forum (Continued)	The Trane Company	Construction Community of Practice Forum (Continued)	The Trane Company	Session 3A	The Trane Company	The Trane Company	The Trane Company	The Trane Company	The Trane Company	The Trane Company
Room 232	Workshop 5 Specifications	Open Meeting of Corps Specifications Steering Committee	Walt Norko	Open Meeting of Corps Specifications Steering Committee (Continued)	Open Meeting of Corps Specifications Steering Committee (Continued)	Walt Norko	Open Meeting of Corps Specifications Steering Committee (Continued)	Open Meeting of Corps Specifications Steering Committee (Continued)	Workshop 5 Specifications	Open Meeting of Corps Specifications Steering Committee (Continued)	Bernie Deneke	Open Meeting of Corps Specifications Steering Committee (Continued)	Bernie Deneke	Open Meeting of Corps Specifications Steering Committee (Continued)	Bernie Deneke
Room 233	Workshop 6 Specifications	Open Meeting of Corps Specifications Steering Committee	Walt Norko	Open Meeting of Corps Specifications Steering Committee (Continued)	Open Meeting of Corps Specifications Steering Committee (Continued)	Walt Norko	Open Meeting of Corps Specifications Steering Committee (Continued)	Open Meeting of Corps Specifications Steering Committee (Continued)	Workshop 6 Specifications	Open Meeting of Corps Specifications Steering Committee (Continued)	Bernie Deneke	Open Meeting of Corps Specifications Steering Committee (Continued)	Bernie Deneke	Open Meeting of Corps Specifications Steering Committee (Continued)	Bernie Deneke



2005 Tri-Service Infrastructure Systems Conference & Exhibition
“Re-Energizing Engineering Excellence”
August 2-4, 2005
St. Louis, MO

Design, Construction and Seepage at Prado Dam

**Douglas E. Chitwood, P.E., G.E.
Embankment Engineer, Prado Dam**



SANTA ANA RIVER MAINSTEM PROJECT PROJECT MAP



SAR Mainstem

Prado Dam


*(after
Modifications)*




Prado Dam: Planned Modifications to the Embankment



Original Embankment: Typical Section



Typical Dam Section





Zoned Embankment






2004 5-19




2004 5 24



Prado Dam: New Outlet Channel



Outlet Channel Plan











25
5:5




25 10:44 AM




2005 4 28






Prado Dam: Staged Construction of Tower and Conduit




Design Considerations: Staged Construction





Stage 1 – Grading Plan



Stage 1 Excavation



Stage 1 Excavation



11 9:04 AM

Cofferdam





2005 2 22



2003 8 5






2003 8 18

Cofferdam II – Miscellaneous Fill with Visqueen Liner



25 2:08 PM

Intake/Control Tower













Received Thursday, 6 January 05

From the National Weather Service...


DISCUSSION:


.TODAY...NO PRECIP EXPECTED.

.FRIDAY...AND CONTINUING ALL THE WAY INTO TUESDAY OF NEXT WEEK...
AN EXTREMELY WET WEATHER PATTERN WILL IMPACT SOUTHERN CALIFORNIA.
A TROPICAL PLUME KNOWN AS THE PINEAPPLE EXPRESS WILL BE FEEDING
MOISTURE INTO A SERIES OF PACIFIC STORMS. HEAVY RAINS WILL CAUSE
URBAN FLOODING AND MOUNTAIN MUDSLIDES. SOME RIVERS WILL BE
SUSCEPTIBLE TO OVERFLOW. **THIS WEATHER PATTERN LOOKS SIMILAR TO
THE ONE THAT PRODUCED THE FLOODS IN THE YEAR 1969.** 50KT WARM
MOIST SW WINDS FROM 5000 TO 10000 FEET ENSURES THAT ALL SOUTH AND
WEST FACING MOUNTAIN SLOPES WILL GET HUGE STORM TOTALS FOR THE 5
DAY PERIOD ENDING TUESDAY.

Prado Dam Operation

Jan 1-25, 2005







JAN 10 2005



JAN 11 2005







JAN 11 2005
















Lean Clay

**Sands and gravels –
increasingly coarse with
depth**

**Very coarse alluvium: gravel,
cobbles and boulders**

Surface of top of Bedrock

2004 1 15




2005 1 19




A stability analysis was conducted by the Los Angeles District Geotechnical Group on the “Thin Section” in December 2003. Among other things, the reported concluded:

“Catastrophic failure due to seepage will not occur as gradient would be much less than critical”


Stage 1 – Grading Plan




Simplified Plan View – Left Abutment




Simplified Plan View – Left Abutment




Simplified Plan View – Left Abutment



Cross-Section through Thinnest Section of Left Abutment





- 
- A photograph of a steep, layered rock face, likely a dam or a quarry wall. The rock shows distinct horizontal sedimentary layers. A yellow arrow points to a dark, vertical seepage point on the left side of the face. The top of the rock face is covered with green vegetation. At the bottom, there is a concrete structure with vertical rebar and a drainage grate.
- 2 gpm of seepage
 - Water cloudy, but not muddy
 - Flow rate, clarity constant

2005 1 14

LA District's Opinion on the Seepage

- Predictable, given the site geology
- Quantity of seepage increased as the saturation front developed
- Low head, low exit gradient
- No cause for concern, but “V-Trench” must be monitored



Small leak, big response

Easy repair needed when water seeps from Prado Dam after recent deluge, prompting Corona, O.C. evacuations.

By PAT BRENNAN
and AMANDA BECK
THE ORANGE COUNTY REGISTER

A leak at Prado Dam on Friday that initially worried city and county officials, prompting evacuations, turned out to be small and relatively easy to repair. But it served as a powerful reminder of the enormous force of the water that fell on Southern California during more than four days of rain that rapidly filled the basin behind the dam, just northeast of Orange County.

Q: What caused the leak?

A: Construction crews with a contracting firm, Yeager-Skanska Inc. in Riverside County, are raising the dam by 28 feet to provide increased flood protection for Orange County.

They are also installing a



cial. Early Friday morning, Army Corps engineers thought there could be a small chance that the leak

OVERFLO

An outlet Prado Dam releases water at high capacity Friday, when a leak at the dam caused evacuations of more than 2,000 in nearby homes. The leak, in the face of the dam, developed after heavy flow from the recent storm filled a pit is normally placing pressure on the dam.

BRUCE
CHAMBERS,
THE REGISTER

Prado Dam springs a small leak

A small leak in Prado Dam prompted evacuations of more than 2,000 people Friday. The leak, in the

**Floods and
flood control**

1,000 people evacuated by Corona dam

State: Seepage threatened to flood area; release eases pressure.

By Ryan Pearson
Associated Press

CORONA — Authorities released a fierce, brown river of water from a Riverside County dam and evacuated more than 1,000 people from its path Friday after a temporary earthen barrier at the site began seeping water.

The U.S. Army Corps of Engineers unleashed more than 10,000 cubic feet of water per second to relieve pressure on the earthen dam 50 miles east-southeast of Los Angeles after more water than usual began pushing through the dirt of a temporary coffer dam that is protecting workers who are extending and raising the dam.

"That's like a swimming pool every second," Corona Mayor Darrell Talbert said.

The water gushed into the Santa Ana River, whose banks were deep enough to handle the flow without flooding, said Lt. Col. John Guenther, deputy commander of the



Residents leery over returning

CONTINUED FROM A1

Officials with the Army Corps of Engineers, which had been raising the dam to increase flood protection, said they were satisfied with the repair job, adding that the seepage of as much as 10 gallons a minute was minor and didn't threaten the dam's safety.

"The pressure behind the dam was the most ever, more than it's had since it's been built," spokesman Fred-Otto Egeler said. "We had to release pressure from the dam but there was no imminent danger. It wasn't us who declared it a disaster."

The seepage developed Thursday night after weeks of heavy rain raised the water above a temporary barrier called a cofferdam that was designed to protect workers and the construction project.

Water spilled over the cofferdam and put pressure on a naturally occurring embankment of bedrock, gravel and soil alongside the dam. Earthmovers had carved into the embank-



STOPPING A LEAK: Seepage was discovered Thursday on the downstream face of Prado Dam where construction was being done on the new intake gate and outlet works. The Army Corps of Engineers took immediate steps to correct and repair the problem.

The problem:

- The temporary dirt cofferdam was built 65 feet high to keep water out of an area excavated for construction.
- Recent heavy rains caused Prado Reservoir to rise to 67.4 feet, which flooded the area.
- Water seeped through the hill that is part of the earthen dam.

The solution:

- Water being released from the dam has been increased from 5,000 to 10,000 cubic feet per second to drop the reservoir level and relieve pressure on the dam.
- The face of the dam where seepage has been found is being shored up with additional dirt.
- The seepage area is being reinforced with a fine mesh called geotextile to keep it stabilized.



but it's good to be informed," Trifunac said. "I don't want to scare you or leave the wrong impression, but dams are complex structures and it takes a lot of looking at details to know what is going on."

If he lived downstream from the Prado Dam, Trifunac said, "I would invite some very knowledgeable people who design dams to give a talk."

The Prado Dam was built in 1941 to protect then-agricultural Orange County from repeated floods, and that protection enabled the later suburbanization of that region.

David Moreno recalled his father's escape in the late 1930s from a flood that killed a thousand head of cattle and forced his family from the rural town of Prado.

"He had to run for his life," said Moreno, 54, of Norco. "From the time they could get out of the house and climb to where Highway 71 is, it flooded that quick."

The Army Corps of Engineers

VOL 10 NO 21 JANUARY 28-FEBRUARY 3 2005 ~ OCWEEKLY.COM ~ SERVING THE ARTS & CULTURE OF ANAHEIM SINCE 1985

BATTLE OF THE BOONDOGGLES (LIGHT-RAIL DIVISION) • **DON'T BLAME GOD** IF PRADO DAM BREAKS
NU-METAL GODS HELMET • **THE MAN WHO LOVED TWO BRAINS:** SONTAG AND KAE

OC WEEKLY

FREE



NECKFACE'S DEVIL,
THOMAS CAMPBELL'S ABSTRACTS
AND ED TEMPLETON'S
SAD LITTLE MONSTERS
HELP MAKE

Events of Thursday Evening, 13 January 2005


- **1500 hrs.** I inspect area and note the seepage area had expanded (approx 200 sq ft) but no velocity increase. Rate approximately 20 gpm. No piping of fines were observed. Approximately 2 gpm still out of V-trench. I met with YSI CQC and earthwork foreman to discuss potential actions should situation deteriorate. Briefed RE that I did not see a problem at this time.
- **1700 hrs.** I leave site for the evening.
- **1730 hrs.** At request of YSI CQC representative, their geotechnical consultant arrives to inspect site. He did not share my confidence.
- **1930 hrs.** Corps Dam Expert, after speaking with Contractor's consultant, understands that seepage was now "15 times greater than 24 hours ago, that it contained fines, that headward erosion and sloughing were observed along the gravel and cobble layer and that the consultant believes a stability berm is needed immediately."
- **1930 hrs.** Speaking to RE, Corps Dam Expert concurs with consultants recommendation to mobilize the contractor's equipment to begin construction of the stability berm and increase discharge to 10,000 cfs.

Events of Thursday Evening, 13 January 2005

- **2022 hrs.** Reservoir Operations begin to ramp up releases.
- **2100 hrs.** I returned and found no significant change in seepage. Request my supervisor and Byron Rathbun (7 Oaks Dam embankment engineer) to come to the site and provide additional opinions.
- **2200 hrs.** Contractor requests California Highway Patrol assist with traffic control when they arrived at the dam. Corona PD hear CHP radio traffic about closing Hwy 71 to get additional construction equipment to Prado and informed the Corona Fire Department.
- **2200 hrs.** Mr. Rathbun and Mr. James Farley, Chief of Soils Design and Materials Section, arrived and inspected the site. Both concurred that the seepage did not merit mitigating measures at that time.
- **2300 hrs.** District Commander directs RE to begin construction of the buttress for preventative measures.

So why did Prado make the news?

1. Extremely large event – record 5-day inflow
2. Inaccurate information
 - Seepage volume increased, not seepage velocity
3. Incorrect assessment
 - GE believed seepage to be carrying fines.
 - Mistook a small localized slump for headward erosion
 - Post-La Conchita, he did stability analysis.
4. Unnecessary recommendation – lead to emergency mobilization
5. Poor communications with locals



BUTRESS FILL SECTION
SCALE: 1" = 20'





2005 1 15









Dung



Yes ☐

No ☐

Yes ☐

No ☐

Yes ☐

No ☐

Yes ☐

No ☐

Lessons Learned

1. Anticipation: I should have anticipated that this could be a concern and have fully briefed the RE
2. Coordination: Even experts need to work through people experienced at the site
3. Communication: We did a poor job apprising the locals of what we were doing and why

Thank you



2005 2 23

Dynamic Testing and Numerical Correlation Studies for Folsom Dam

Ziyad Duron (Harvey Mudd College)

Enrique E. Matheu (USACE Engineer Research and Development Center)

Vincent P. Chiarito (USACE Engineer Research and Development Center)

Michael K. Sharp (USACE Engineer Research and Development Center)

Rick L. Poeppelman (USACE Sacramento District)

Presented by

Enrique E. Matheu, PhD

Geotechnical and Structures Laboratory

Engineer Research and Development Center

Vicksburg, MS



US Army Corps
of Engineers

2005 Tri-Service Infrastructure Systems Conference and Exhibition

St. Louis, MO – August 2-4, 2005

U.S. Army Engineer Research and Development Center

Introduction

- **Full-Scale Dynamic Testing**

- Dynamic testing can be effectively used to identify the main dynamic response characteristics of concrete dams.
- These tests can provide information regarding the relative importance of interaction mechanisms involving the dam, the impounded reservoir, and the underlying foundation region.
- Test results can be used to assess the limitations of different numerical models employed to predict the response of the system under severe seismic excitations.
- However...

Field testing of concrete dams has not been widely embraced in the US as an essential component in the process of evaluating the seismic performance of these structures.



Introduction

• Folsom Dam Description



- Design/construction by USACE (1948-1956), transferred to USBR (1956)
- Maximum height of gravity section is 340 ft with a crest length of about 1,400 ft.
- 28 monoliths, 50 ft wide each.
- Main spillway: 5 ogee monoliths, two tiers of 4 outlets. Emergency spillway: 3 flip bucket monoliths.
- Embankment wrap fill and wing dams



US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Introduction

- **Folsom Dam Dynamic Testing Program**


- Research study conducted by the U.S. Army Engineer Research and Development Center (ERDC) consisting of a series of field tests and numerical analyses performed on Folsom Dam, California.
- Ambient surveys and forced vibration tests were conducted to determine the main dynamic characteristics of the dam-foundation-reservoir system.
- Numerical studies of the observed response behavior were performed using 2D and 3D models of the system.



Ambient Survey

- **Survey Description**

- Ambient survey conducted in March 2004.
- At each monitored location, ambient acceleration responses excited by environmental conditions were monitored over a 7-minute interval.
- Ambient hydrodynamic pressure responses were also acquired behind monoliths 14 and 21.




US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center



Ambient Survey

- Sample Signals



Typical peak acceleration levels range from 0.5 milli-g's at the crest of Monolith 11 to 0.1 milli-g's at the crest of Monolith 1

Noise threshold: 1 micro-g for Honeywell Q-Flex accelerometers QA-700, QA-750, and QA-900.



US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center


Ambient Survey

• Results

- Spectral analysis conducted using the specially developed software *iDAMS*.
- Both power spectral density and coherence must be examined.
- Spectral response of Monolith 10 associated with relatively wide regions of coherence approaching unity between 4-6 Hz and between 8-10 Hz.



US Army Corps
of Engineers




U.S. Army Engineer Research and Development Center


Ambient Survey

- Results



- Analyses of global measured responses indicated near-monolithic behavior in the dam below 10 Hz.



4.64 Hz



5.49 Hz




US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Ambient Survey

- **Results**

- The portion of the roadway that spans the spillway section appears to respond with amplified motions in the vicinity of 10-12 Hz.
- The response of the bridge deck above 10 Hz may require further investigation in order to determine whether it would remain operational during a seismic event.



10.01 Hz





US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Forced Vibration Tests

- **Test Description**



- Results from the ambient survey provided confidence that a single eccentric mass vibrator (shaker) would excite steady-state responses in the dam, reservoir and adjacent foundation.
- Forced vibration tests conducted at Folsom Dam in June 2004.
- Shaker locations:
 - Monoliths 11, 14, 21



Forced Vibration Tests

- **Acceleration Frequency Responses**

- Peak below 5 Hz corresponds to the fundamental symmetric resonance at 4.65 Hz.
- Large peak below 6 Hz corresponds to the second fundamental resonance at 5.46 Hz.




US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Forced Vibration Tests

- **Dominant Responses**



- Global comparison of acceleration response functions measured with shaker mounted on Monolith 11 (crest).
- Below 10 Hz, second resonance dominates (Monoliths 4-12).
- Above 12 Hz, response clearly dominated by spillway behavior.



Forced Vibration Tests


- **Crest Responses for Monoliths 1-10**

- Stationary fundamental resonance at 4.65 Hz.
- Sliding character of second system resonance beginning at 5.46 Hz.
- Largest and narrowest resonance peak at Monolith 10.
- Smaller and wider peaks for monoliths closer to the abutment.



Forced Vibration Tests


- **Influence of Elevator Tower**
 - Tower exhibits fundamental resonance near 11.6 Hz (blue curve) that coincides with an anti-resonance in the dam (red curve) indicated by the acceleration response acquired 60 ft below the crest in Monolith 11.




Forced Vibration Tests

- System Characteristics


Resonant Frequency (Hz)	Half-Power Method	Pole Fitting
4.65	-	4.0-6.5 %
5.46	5.6-8.4 %	4.8-7.0 %
6.24	-	4.0-8.0%
7.16	6.3-8.0%	4.0-7.8%
8.00	-	-
8.87	-	-



4.65 Hz



5.46 Hz





US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Forced Vibration Tests

- Reservoir Response Characteristics



$$H_{\text{eff}} = \frac{C_w}{4f_{\text{reservoir}}} = \frac{4720 \text{ ft/sec}}{4 \cdot 5.23 \text{ Hz}} \cong 226 \text{ ft}$$




US Army Corps
of Engineers


U.S. Army Engineer Research and Development Center

Forced Vibration Tests

- Reservoir Response Characteristics



Fundamental resonance for hydrodynamic pressure profile



Second resonance for hydrodynamic pressure profile



US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Numerical Correlation Studies

- Preliminary Study Objectives


- To develop numerical models that represent the dam, reservoir, and foundation to capture observed response behavior acquired during forced vibration tests at Folsom Dam (“baseline model”).
- Key issues:
 - Dam-foundation interaction
Consideration of foundation flexibility effects
 - Dam-reservoir interaction
Incorporation of hydrodynamic effects
 - Tower influence on dam response
Consideration of vibration reduction by dynamic tuning



Numerical Correlation Studies



- **Baseline Model Assumptions**

- Linear elastic behavior assumed throughout system.
- 3D dam model (8,103 solid brick elements).
- Includes tower, roadway, and varying spillway monolith geometries.
- Foundation region idealized as massless (stiffness only contribution).
- Reservoir modeled using Westergaard's simplified model to define added masses along upstream face.
- Reservoir elevation 430'.



Numerical Correlation Studies

- 2D Models (SAP2000)




Mode	Natural Frequencies [Hz]			
	Monolith 14		Monolith 21	
	Rigid	$E_c/E_f = 0.25$	Rigid	$E_c/E_f = 0.25$
1	5.23	4.68	5.00	4.67
2	12.31	10.80	10.50	9.52
3	14.63	12.43	16.80	14.37
4	19.96	18.31	18.98	16.95
5	25.73	24.40	28.53	26.09



Numerical Correlation Studies

- 3D Model (SAP2000)



Dam concrete:

Modulus of elasticity (E_c) = 849,000 Kips/ft²

Poisson's Ratio = 0.19

Foundation rock:

Modulus of elasticity (E_f) = 1,584,000 Kips/ft²

Poisson's Ratio = 0.30

$E_c / E_f = 0.54$



US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Numerical Correlation Studies

- Measured Resonances vs Computed Natural Frequencies

Ambient Vibration Survey Resonant Frequency (Hz)	Forced Vibration Survey Resonant Frequency (Hz)	Natural Frequency (Hz) (SAP2000)
4.64	4.65	4.67
5.49	5.46	5.35
Not Observed	Not Observed	5.91
6.47	6.24	6.56
7.32	7.16	7.47
8.18	8.00	8.40
8.91	8.87	8.82



Numerical Correlation Studies

- **SAP2000 and EACD-3D (Empty Reservoir Condition)**


Natural Frequency (Hz)		
SAP2000	EACD-3D	EACD-3D (Adjusted)
5.71	6.06	5.71
6.29	6.67	6.28
6.84	7.30	6.87
7.45	8.01	7.54
8.61	9.41	8.86

- **EACD-3D will be used to quantify water compressibility effects including energy absorption due to sediments at the bottom of the reservoir.**
- **The flexibility of the foundation rock can be included but associated inertia and damping effects are ignored.**




Numerical Correlation Studies

- Influence of Elevator Tower



Comparison of measured and
predicted response
Level 5 (dam)



Comparison of measured and
predicted response
Level 9 (tower)




US Army Corps
of Engineers


U.S. Army Engineer Research and Development Center

Numerical Correlation Studies

- Elevator Tower as Tuned Vibration Absorber



Tuned vibration absorber model




The blue line represents the response of the main system without the vibration absorber. The red line represents the response of the main system including the presence of the absorber.

The response indicates two “split” resonances that straddle the original fundamental frequency.




Numerical Correlation Studies

- Surface Plot Comparison of Crest Acceleration Responses



Tower included



Tower removed




US Army Corps
of Engineers


U.S. Army Engineer Research and Development Center

Numerical Correlation Studies

- Foundation Flexibility Effects at Monolith 14



Measured response



Numerical model



Summary

A series of dynamic tests have been completed at Folsom Dam to gain detailed understanding of its dynamic response characteristics, including dam-foundation and dam-reservoir interaction.

Dam response behavior observed along the crest indicated monolithic dam response below 10 Hz.

The elevator tower acts as a vibration absorber tuned near 11 Hz and affects dam response across all monoliths.

Evidence of foundation flexibility was observed at the base of Monolith 14.

Fundamental reservoir resonance at 5.23 Hz influences the fundamental system resonance at 4.65 Hz.

A preliminary numerical correlation study indicated that the 3D model is capable of capturing several major response characteristics at Folsom Dam.

Above 6 Hz, a variety of influencing factors will require further investigation including water compressibility effects and appropriate damping values for resonances at higher frequencies.



Acknowledgments

This research study was the result of a joint effort by personnel from Harvey Mudd College (HMC); ERDC Geotechnical and Structures Laboratory (GSL), and ERDC Information Technology Laboratory (ITL).

The research work described herein was performed by Prof. Ziyad H. Duron, Ms. Angela Cho, Mr. Eric Flynn, Mr. Nicolas Von Gersdorff, Mr. Robert Panish, and Mr. Nate Yoder, HMC; Mr. Vincent P. Chiarito, Dr. Enrique E. Matheu, and Dr. Michael K. Sharp, GSL; and Mr. Bruce Barker, ITL.

Prof. John F. Hall, California Institute of Technology provided technical review.

Mr. Rick L. Poeppelman, SPK, was the technical monitor.



US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center



Enrique E. Matheu, PhD
Engineer Research and Development Center
3909 Halls Ferry Road, ATTN: CEERD-GS-E
Vicksburg, MS 39180
Phone: 601-634-2692
enrique.e.matheu@erdcd.usace.army.mil



US Army Corps
of Engineers

U.S. Army Engineer Research and Development Center

Fern Ridge Dam, Oregon

Seepage and Piping Concerns
(Internal Erosion)

SPRA Training – 25 May 2005

2002 and 2003 OBSERVATIONS



Location of Depressions

Sinkholes on D/S face




September 2002

Station 44+00

February 2003



Sinkholes on D/S face



Station
20+00

February 2003


Sinkhole on D/S face

Station
16+00




February 2003


Plan View (Sta. 0+00 – 25+00)




Plan View (Sta. 25+00 – 50+00)




Plan View (Sta. 50+00 – 70+00)




Fern Ridge Cross Section



Details of D/S Embankment Structure




Drain System Details



Note:


Pipe shall be 8"-14 gauge corrugated metal with bituminous coating. Main shall be perforated bottom 120" with 3/8" holes @ 1 1/2" centers in valley of corrugations except at joints. Joints shall be 1/2 circle band, 7" width, riveted to pipe for 1 corrugation. Joints shall be locked by means of an angle iron riveted to abutting sections and bolted. After bolting all parts of joint shall be coated with same bituminous material as pipe. Connections to laterals shall be made with standard tee sections.




Note:

On the crest of the dam between stations 9+07.75 and 68+80 and stations 2+80 and 5+90.5 a 4" thick top coarse (49) shall be placed.


Sediment Deposition Rate and Drain Flow versus Time



Gradation Graph



U.S. Standard Sieves



Station 14+40

At Pool Elev 373.5 (MAX. CONS. POOL)

For FOUNDATION PIPING/EROSION FM


$$i_{BC} = \frac{\Delta H}{\Delta L} = \frac{21.5}{50} = .45 \text{ to } .50$$

$$\lambda_{wc} = \frac{21.5}{2} = \underline{10 \text{ to } 11}$$

Summer 2004


$$\mu_{BE} \approx 1.0 = \frac{\Delta H}{\Delta L} \approx \Delta L = 21.5'$$

Say 20'***




Continuation of Piping Failure

Fern Ridge Current Conditions




Questions?



**U.S. Army Corps
of Engineers**

Status of Portfolio Risk Assessment


**Eric Halpin, PE
Special Assistant for Dam Safety
HQ US Army Corps of Engineers
August 2005**



U.S. Army Corps
of Engineers

Purpose


- **Describe Program Management Plan for Implementing Risk and Reliability:**
 - **Scope of Work (Reservoir & Navigation Dams)**
 - **Roles & Responsibilities**
 - **Budget**
 - **Schedule**



U.S. Army Corps
of Engineers

Scope of Work

General Objectives	Team & Leader
Ways: Tools & Methods	Methodology Team <i>Anjana Chudgar</i>
Ways: Policy & Planning	Dam Safety Steering Committee <i>Charles Pearre</i>
Means: Human and Financial Resources	Program Management Team <i>Andy Harkness</i>
Ends: Oversight & Decisions	Senior Oversight Group <i>Eric Halpin</i>



U.S. Army Corps
of Engineers


Senior Oversight Group

- **Team Members:**

- Eric Halpin, Leader
- Harry Kitch, HQ
- Barry Holliday, HQ
- Programs, HQ
- Bruce Murray, LRL
- Tommy Schmidt, SWD
- John Bianco, NAD
- Jeff Schaefer, LRL
- Dave Schaaf, LRL
- Jeff McClenatham, NWO
- Jerry Webb, HQ

- **Specific Objectives:**

- Overall Planning and Oversight of Other Teams
- Annual Interpretation & Recommendations from Risk Assessments
- Strategic & Operational Guidance on:
 - Policy
 - Methods
 - DS Program Changes
 - Long Term Management & Staffing Approach



U.S. Army Corps
of Engineers


Methodology Team

- **Team Members:**

- Anjana Chudgar, HQ Lead
- USBR Representative
- Dr. David Bowles
- Cadre Representatives (3)
- HQ E&C CoP Leader
- MSC Representative
- Wayne Jones, ERDC
- Mike Grounds, DSPMT

- **Objectives:**

- Update & Revise SPRA Tool as necessary
- Develop PRA Tool Using USBR Method as Template
- Provide Recommendations to Policy Team
- Develop Site Specific Risk Assessment Tool



U.S. Army Corps
of Engineers


Policy & Planning Team

- **Team Members:**

- Charles Pearre, HQ Leader
- Rob Taylor, LRD
- Milt Meyers, ERDC
- Laila Berre, NWD
- Dan Rodriguez, NAD
- Dwayne Lillard, SPA
- Duane Stagg, MVD
- Bob Fulton, SAD
- Tats Hirata, POD
- Sue Gehrt, NWK
- Brent Trauger, SAJ

- **Specific Objectives:**

- Complete Review and Edits on SPRA ETL
- Develop ETL on PRA Methodology
- Re-Engineer USACE Dam Safety Program with Risk and Reliability Approach:
 - Periodic Inspections
 - Instrumentation
 - Training
 - Exercises
 - EAPs



U.S. Army Corps
of Engineers


Program Management Team

- **Team Members:**

- Andy Harkness, Lead LRP
- Charles Pearre, HQ
- Operations CoP, HQ
- Operations CoP, District
- Joseph Bittner, HQ
- Michael Jordan, SWG
- Mark Mugler, ASA Advisor

- **Specific Objectives:**

- Budget, Manage, and Execute Required Funding of All R&R Activities
- Coordinate and Develop All Human Resources
- Schedule and Coordinate All Major Program Milestones
- Manage All Outsourced Support
- Manage ITR and Peer Review Efforts




U.S. Army Corps
of Engineers

Program Schedule

Activity	FY05	FY06	FY07	FY08	FY09	FY10
SPRA Design	█					
SPRA Deployment		█	█	█		
PRA Design		█				
PRA Deployment			█	█	█	█
Site Specific RA Design			█			
Steady State Staff				█	█	█
Policy & Program		█	█	█	█	
Oversight	█	█	█	█	█	█

Steady State




U.S. Army Corps
of Engineers

Budget

- **FY05: \$1.62 M**
- **FY06: \$ 3.55 M Requested and Being Justified/Briefed**
- **FY07: \$ 4.3 M Being Justified/Briefed**
- **FY08 and Beyond: To be Determined by Program Management Team**





**US Army Corps
of Engineers**

Los Angeles District
Portland District

SEVEN OAKS DAM

Outlet Tunnel Invert Damage



Santa Ana River Mainstem Project



US Army Corps
of Engineers®
Los Angeles District





Seven Oaks Dam

- Authorized under WRDA 1986, 99th Congress 2nd Session, P.L. 99-662
- Flood Control Purpose
- Operate in Tandem with d/s Prado Dam
- Non-Federal Sponsors:
 - Orange County Flood Control District
 - San Bernardino County Flood Control District
 - Riverside County Flood Control and Water Conservation District



Seven Oaks Dam





Seven Oaks Dam

Pertinent Data

- River Santa Ana River
- County and State San Bernardino County, California
- Purpose Flood Control
- Drainage Area 177 mi²
- Type Rolled, zoned, earth and rockfill
- Crest elevation (excluding overbuild) 2,610 feet, NGVD
- Foundation elevation at dam axis 2,060 feet, NGVD
- Maximum height above foundation
at dam axis 550 feet
- Freeboard 5.3 feet
- Crest length 2,760 feet
- Crest width 40 feet
- Crest overbuild varies from 0 to 3 feet
- Downstream 1.8H to IV
- Upstream 2.2H to IV
- Total embankment volume 38,372,510 cubic yards



Seven Oaks Dam

Pertinent Data

- Debris pool (year 1) 2,200 feet, NGVD
- Debris pool (year 100) 2,300 feet, NGVD
- Reservoir design flood pool 2,580 feet, NGVD
- Probable maximum flood pool 2,604.7 feet, NGVD

Gross capacity

- Reservoir design flood pool (spillway crest) 147,970 acre-feet
- Probable maximum flood pool 169,177 acre-feet
- Top of dam 174,609 acre-feet

Storage allocation (below spillway crest)

- Flood control 115,970 acre-feet
- Sedimentation (100 year storage) 32,000 acre-feet



Seven Oaks Dam

Pertinent Data

Reservoir design flood (general storm)

- Total volume (4 day) 115,000 acre-feet
- Peak inflow 85,000 ft³/sec
- Peak outflow 7,000 ft³/sec

Probable maximum flood (general storm)

- Total volume 326,000 acre-feet
- Peak inflow 185,000 ft³/sec
- Peak outflow 180,000 ft³/sec



Chronology

- 1980 Phase I General Design Memorandum
- 1988 Phase II GDM
- 1989 Construction of Pilot Tunnel
- 1991 Partial Intake Structure
- 1992 Diversion Tunnel
- 1999 Dam and Outlet Works
- 2005 High Flow Testing and Tunnel Damage

Seven Oaks Dam






SEVEN OAKS DAM

OUTLET WORKS PROFILE

OUTLET WORKS

- 1,600-FOOT LONG TUNNEL
- 200-FOOT HIGH INTAKE STRUCTURE
- 300-FOOT HIGH AIR SHAFT
- GATE CHAMBER
- EXIT CHANNEL
- PLUNGE POOL




EMBANKMENT CROSS SECTION

DAM

- 550-FOOT HIGH
- 3,000-FOOT LONG
- 40-FOOT WIDE AT CREST
- 2,000 FEET FROM U/S TOE TO D/S DOT

ZONE	PURPOSE
CORE	WATER BARRIER
TRANSITION	DRAINAGE, STABILITY, AND ECONOMICAL USE OF EXCAVATED MATERIALS
ROCKFILL	STABILITY AND ECONOMICAL USE OF EXCAVATED MATERIALS
SHELL	DRAINAGE, EROSION CONTROL, AND STABILITY





Embankment and Intake Structure






Intake Structure





Gate Chamber





Hydraulic Gates



LOOKING U/S RO GATE FRAMES
& ATTACHED BONNETS & CYLINDERS
FORMWORK FOR GATE PASSAGES

Sep1988



Access Tunnel





Embankment and Plunge Pool





Hydraulic Design Requirements

- High velocity flow cavitation concern
- 1:25 physical model testing at WES/ERDC
- Flow aeration
- Embed pressure transducers in tunnel for flow testing
- High flow testing to verify design



WATER YEAR PRECIPITATION SUMMARY

Summary by River Basin (% of Historic Average)
For the period Oct 1, 2004 to Jun 30, 2005

	Oct-Jun	Season
• Santa Barbara Area	221	217
• Ventura – Los Angeles Area	236	231
• Santa Ana River	226	217
• San Diego Area	190	183

Ref: California Cooperative Snow Surveys
(<http://cdec.water.ca.gov/cgi-progs/iodir/PRECIPSUM.2005>)





























High Pool El.2392(March 2005)



High Pool El.2392(March 2005)



High Pool El.2392(March 2005)





Hydraulic Testing

Table 1 Testing Schedule and Maximum Discharge Rates

Testing Schedule Feb 17 - Mar 9		Testing Pool (ft)	Range of Gate Openings	Maximum Test Flow Rate (cfs)	Maximum Operational Flow Rate* (cfs)
21-Feb	MDL Test	2373	10%-100%	135	120
22-Feb	MDLE Test	2373	100%	115	100
25-Feb	Low Flow Test	2383	0.25' - 3'	560	700
8-Mar	Right RO Gate Test low Openings	2391	0.5' - 3'	1540	
9-Mar	Right RO Gate Test-High Openings	2392	3.5' - 8' 5'	2000 2520	4900
10-Mar	Combined RO Gate Test**	2390	0.5' - 6.8'	6600	8000

* Maximum Operational Flow Rate is stated in the *Seven Oaks Water Control Manual*, Corps of Engineers, Los Angeles District 2003

Maximum pool for RO gates is 2580 ft, Maximum pool for MDL and MDLE = 2300 feet

Max. opening for two gate operation = 6.8 feet; max. opening for single gate operation = 8 feet

** stricken items were cancelled due to slab failure

Minimum Discharge Line Flow Test



Cone Valves Flow Jet



High Flow Test (9Mar05)



High Flow Test (9Mar05)



High Flow Test (9Mar05)



High Flow Test (9Mar05)



High Flow Test (9Mar05)



High Flow Test (9Mar05)






























What Happen?


- Was it caused by cavitation?
- Debris impact?
- Groundwater uplift?
- Negative air pressure?
- Differential concrete shrinkage?
- Design deficiency?
- Construction defect?
- Earthquake?

“Just the Facts, Ma’am”

Courtesy of Sgt. Joe Friday
“Dragnet” Detective Drama Series
1952-59, 1967-70



SEVEN OAKS DAM







SEVEN OAKS DAM

- Reservoir Height - 291 ft.
- Tower Height - 200 ft.
- U/S Tunnel - 18' dia., 1000' long
- D/S Tunnel - 18' X 18.5', 600' long
- Gate Chamber - 50' dia.
- Air Shaft - 11' dia., 320' vertical, max. $v=140$ fps
- 2 RO Gates - 5' wide X 8.5' high
- 1 Low Flow Gate – 2' wide X 3.5' high
- Max. $Q=8,000$ cfs, max. $v=115$ fps @ RO gates



Downstream Tunnel Plan









Design Assumptions

- Resist external rock and groundwater
- Invert designed as full-depth beam
- High strength silica fume topping for erosion resistance of high velocity flow
- Silica fume bond to base concrete and act monolithically
- No epoxy bonding agent
- No reinforcement across transverse joints



SEVEN OAKS DAM

Investigation and Repair


- Phase 1- Concrete Cores for Visual, Petrography, and Strength Tests
- Phase 2 – Additional Concrete Cores for Visual, Detail Petrography, and Tensile Tests
- Phase 3 – Demolition of Critical Slabs
- Phase 4 - Repair of Critical Slabs
- Phase 5 – Repair of Additional Slabs



Concrete Coring Investigation

(Apr & May05)

67% Cores Debonded





Slab 1 Damage Surface



Fig. 3a – Cracking, delamination, and erosion of Slab 1 surface



Slab 2 Concrete Cores



Fig. 6 – Top surfaces (SFC-CC interface) of Slab 2 cores

Slabs 1 to 17 Typical Concrete Cores



Fig. 9 – Typical failure surfaces on cores from Slabs 7-17

Concrete Cores Investigation

- Phase 1- Concrete Core Testing
 - > Completed – 27 Apr 05
 - > 67 % cores debonded
 - > Compressive strength tests pending
 - > Cursory petrography suggests tensile failure from incomplete bond development due to improper surface preparation or cold joint formation;
 - > Veneer of carbonate deposit


Concrete Cores Investigation

- Phase 2 – Additional Concrete Core Testing
 - > Completed – 4 May 05
 - > 63 % cores debonded
 - > Prelim detailed petrography confirms SC/CC interface exhibits layer of solidified carbonate-based residue;
 - > Inadequate surface roughness for mechanical bonding; weak concrete at interface due higher W/C;
 - > Final report pending

Analysis

- Reservoir at el.2392
- Gate opening at 5.0 ft
- Flow rate 2,520 cfs
- Velocity 130 ft/s
- Stagnation pressure 120 psi, but jet impingement pressure estimated 5 to 10 psi
- Pressure highest at invert joint with wall
- Only 0.7 psi to uplift silica fume layer

Plan View of Damaged Slab Area





Free-Body Diagram of Damaged Slab Cross-section




Figure 24 Tunnel Floor Free Body Diagram



Flow Jet Trajectory




Figure 23 Schematic of Jet Trajectory at Gate Opening 5 feet, Prior to Failure Event



SEVEN OAKS DAM

Tunnel Invert Damage - Cause

- Water Pressure from high velocity flow jet penetrates construction joints.



Tunnel Invert Damage - Cause

- Pressure migrates through seams between poorly bonded to debonded silica fume concrete overlay and substrate concrete and increases.



Tunnel Invert Damage - Cause

- Water pressure under overlay combined with reduced air pressure breaks bond between overlay and substrate concrete, and lifts up overlay.



Tunnel Invert Damage - Cause


- Impact from jet breaks up overlay slab, pulverizes slab into smaller pieces, and completely erodes away edge of overlay.



SEVEN OAKS DAM


Tunnel Invert Repair Plan

- Remove Damaged and Suspect Slabs
- Anchor New Overlay to Base Concrete
- Assure Proper Joint Preparation & Bond Enhancement
- Use Non-Shrink High Strength Concrete





Slab Repair Plan





SEVEN OAKS DAM

Repair Schedule

- Phase 3 – Demolition Critical Slabs 1 to 6

Construction Complete – 5 Aug 2005

- Phase 4 – Repair Critical Slabs 1 to 6

Construction Complete – 30 Sep 2005

- Phase 5 – Demolition and Repair Additional Slabs as Required


Construction Complete – 30 Sep 2006

“Dum Dee Dum Dum
Dum Dee Dum Dum Dum”

Music Theme

“Dragnet” Detective Drama Series

1952-59, 1967-70



1920 - 1982
Creator and
Main Character of
“Dragnet”
TV Series

Picture Courtesy of:
<http://www.amazon.com/exec/obidos/ASIN/092976529X/thefiftieswebsit/>





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Bluestone Dam DSA Anchor Challenges

Tri-Service Infrastructure Systems Conference

Michael McCray, P.G.
(304) 399-5234





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Topics

- ◆ **Brief Overview of Bluestone Dam**
- ◆ **DSA efforts completed to date / ongoing and future efforts**
- ◆ **Lessons learned from the field anchor study**



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Location






US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Features

- ◆ **Concrete gravity dam**
 - 165' high
 - 2060' long
- ◆ **4600 mi² drainage area**
- ◆ **Outlet works**
 - 16 sluices
 - Gated spillway (21)
- ◆ **6 penstocks**



Construction

- ◆ Started in 1942
- ◆ Suspended in 1944 (WWII)
- ◆ Resumed in 1946
- ◆ Completed in 1948
- ◆ Hydropower not implemented
 - Storage re-allocated for flood control
 - Pool elevation reduced from 1490 feet to 1410 feet





Bluestone Dam Overview



Spillway 790' long





Bluestone Dam Overview


◆ Project foundation:

● Valley floor:

- Founded on orthoquartzite or interbedded orthoquartzite and carbonaceous shale


● Abutments:

- Shales
- Siltstone
- Sandstone



DSA Project History

Fault was not removed from monoliths
10 through 12



TOP OF EXISTING DAM - EL 1535


FLOOD CONTROL POOL - EL 1520

POOL OF RECORD - EL 1506

SEASONAL POOL - EL 1410

MONOLITH 12

OVERBURDEN




PMF - EL 1547.8 - OVERTOPPING DAM

PMF - EL 1542.2 - DSA OPTION

TOP OF EXISTING DAM - EL 1535

IFF - EL 1509 TO EL 1517

POOL OF RECORD - EL 1506





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Bluestone DSA Phase 1

◆ Phase I Contract


- Awarded Sept. 2000
- Completed 2004

◆ Project Features

- 2 Lane Bridge
- Thrust Blocks
- Extending Penstocks
- Sacrificial Bulkheads



Bridge



Penstocks

Thrust block







Bluestone DSA – Phase 2A

Crest gate
guide
extensions

Route 20 gate
closure

monolith
(not shown)




Upgrade access
road to stilling
basin

Bluestone DSA – Phase 2B


- ◆ Awarded 31 May 2005
- ◆ Brayman Construction Corporation
- ◆ \$30,000,000



Bluestone DSA – Phase 2B



Bluestone DSA – Phase 2C





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Lessons Learned from the Field Anchor Study

- ◆ Corrosion Protection
- ◆ Drill Hole Alignment



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

2002 Field Anchor Study

◆ Install Four 61 Strand Production Anchors

- Two from top of dam and instrumented (8°)
- Two from face of dam (45°)
- Corrosion protection is 10" corrugated polyethylene pipe 70-mil.
- Bond zones forty feet.
- Stressed lengths 130 to 200 feet.



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Field Anchor Study (cont.)

◆ Install Eight Bond Stress Test Anchors

- 18 strand anchors in 5" holes
- Bond zones 10'
- Load to, or near, bond failure
- 4 lithologies tested
- Parallel lab pull-out tests for comparison



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Lessons Learned from the Field Anchor Study

◆ Corrosion Protection

- Corrugated

- Thickness
- Handling


- Sheathing

- Polyethylene VS Polypropylene
- Handling

Corrosion Protection

◆ Corrugated (Prinsco, Goldline)

- 70-mil (measured at the crown)
 - 84-mil max
 - 56-mil minimum
- 550 ft lengths





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection

Corrugated collapses

- First lift 9 ft
- Second lift 30 ft
 - Collapses at 9 ft and travels up 8 ft
- All lifts reduced to 20 ft





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Smooth Walled HDPE 1/2" Thick





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

HDPE Welded





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection



Corrosion Protection

◆ Corrugated (Prinsco, Goldline)

- 4-mm (157-mil)
- Manufactured in maximum 60 ft sections

◆ Smooth Wall (CPChem, Driscoplex 4100)

- 0.5 inch





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection

◆ Smooth Wall Collapse

- First lift 10 ft
- Second lift 41 ft
- Third lift 119 ft (to the surface)
 - Collapse at 51.5 ft



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection

- ◆ Critical buckling pressure for 10" diameter, 70-mil corrugated: 19 PSI
- ◆ Critical buckling pressure for 10" diameter, 157-mil corrugated: 59 PSI
- ◆ Critical buckling pressure for 10" diameter, 0.50-inch smooth: 19 PSI



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection

Specifications call for a 100-mil corrugated

- ◆ **Critical buckling pressure for 10” diameter, 100-mil corrugated: 39 PSI**



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Installation of Corrugated





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Installation of Corrugated

Specifications call for a simple falling head test on the installed, but ungrouted corrugated.

Loss of less than 2.75 gallons in 10 minutes at 5 psi head shall constitute a watertight encapsulation.



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection

Field Fix of Polyethylene





9.24.20



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Tendon Installation





**US Army Corps
of Engineers**
Huntington District

One Corps, One Regiment, One Team







US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Corrosion Protection

Specifications call for a polypropylene hot-melt extruded coating. Polypropylene is much tougher than polyethylene sheathing but does cost more.



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Alignment Tolerance Field Anchor Study

The scope specified a minimum drill tolerance of 1 in 150. Each drilled hole was surveyed for positional accuracy by the Baker-Hughes INTEQ using the Seeker™ Surveying System.

Survey accuracy

1 in 700 8-degree holes

1 in 300 45-degree holes



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Starter Guide



Sub-Bearing Plate and Trumpet





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Installation and Alignment





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Installation and Alignment





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Installation and Alignment





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

15" Hammer





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Alignment Tolerances


◆ Crest Anchors

- 1 in 110 feet


◆ Anchors on downstream slope

- 1 in 20 feet

Up-Down Deviation from Intended Location Due to Drift



Left-Right Deviation from Intended Location Due to Setup Error





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Alignment Tolerances

Each bidder was given a video documenting the lessons learned from the 2002 field anchor study and a copy of a report on directional drilling and bore hole alignment measurement technology.



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Alignment Tolerances

Specifications call for each anchor hole to be surveyed using a rate gyrocompass, or equal equipment. If the hole alignment is not within these tolerances, the hole shall be backfilled and redrilled at the contractor's expense.



**US Army Corps
of Engineers**
Huntington District

One Corps, One Regiment, One Team

Questions?

Michael McCray

Phone (304) 399-5234


E-mail mikem@mail.orh.usace.army.mil

Foundation Conditions

◆ Construction Events


Fault was only partially removed from monoliths 13 and 14

- * Fault was not removed from monoliths 10 through 12




DSA Project History

Fault was not removed from monoliths
10 through 12




Up-Down Deviation from Intended Location Due to Setup Error





US Army Corps
of Engineers



CANTON DAM SPILLWAY STABILITY



Is a Test Anchor Program Necessary?

One Corps Serving The Army and the Nation



US Army Corps
of Engineers




CANTON DAM SPILLWAY STABILITY

- Background and History
- Determining Anchor Capacity
- Investigation and Test Anchor Program
- Summary

One Corps Serving The Army and the Nation



US Army Corps
of Engineers




CANTON DAM SPILLWAY STABILITY

- Background and History


One Corps Serving The Army and the Nation



US Army Corps
of Engineers




CANTON LAKE LOCATION



One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM



One Corps Serving The Army and the Nation



US Army Corps
of Engineers


CANTON DAM



One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM


PROJECT DESCRIPTION

- **Rolled Earthfill Embankment with a Length of 15,140 ft. and max. height of 73 ft.**
- **Gate Controlled Concrete Chute Spillway with 16 - 40 ft. wide by 25 ft. high Tainter Gates with a Total Capacity of 274,000 cfs.**
- **Outlet Works Consists of 3 - 7 ft. wide by 12 ft. high sluice gates.**
- **Downstream Channel Capacity is Approx. 1000 cfs.**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM


PERTINANT DATA

- **Top of Dam** **1648.0**
- **Top of Flood Control Pool and
Top of Spillway Gates** **1638.0**
- **Top of Conservation Pool** **1615.4**
- **Pool Restriction** **1626.0**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM DAM SAFETY ISSUES

- **HYDROLOGIC DEFICIENCY**
- **SEISMIC DEFICIENCY**
- **SEEPAGE DEFICIENCY**
- **SPILLWAY STABILITY**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers


CANTON DAM SPILLWAY STABILITY



One Corps Serving The Army and the Nation



US Army Corps
of Engineers



FOUNDATION MATERIALS

– PERMIAN RED BEDS


- RUSH SPRINGS SANDSTONE
- DOG CREEK SHALE
 - COMPACTION SHALE
 - POORLY INDURATED
 - GYPSUM LAYERS
 - SOFT LAYERS
- BLAINE FORMATION
 - COMPACTION SHALE
 - 2 MASSIVE GYPSUM/ANHYDRITE LAYERS

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

DOG CREEK SHALE STRENGTH CHARACTERISTICS




- **OVERCONSOLIDATED**
- **DILATES WHEN SHEARED (AT LOWER CONFINING PRESSURE)**
- **LOWEST STRENGTHS 20-30 FEET, OR 1570-1580 ELEVATION, AND BELOW 50 FEET**
- **HIGHEST STRENGTHS BETWEEN 30 AND 40 FEET**


One Corps Serving The Army and the Nation



US Army Corps
of Engineers




DATA FROM ALL SHEAR TESTS



One Corps Serving The Army and the Nation



US Army Corps
of Engineers



TECHNICAL CONCERNS


- **WEAK LAYERS IN FOUNDATION**
 - GYPSUM SEAMS
 - OTHER SOFT SEAMS
- **DESIGN SHEAR STRENGTH**
 - USE OF COHESION
- **DRAINAGE**
 - 50 PERCENT EFFECTIVE
 - 0 PERCENT EFFECTIVE

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

LISTING OF SAFETY FACTORS





•	DATE	C	PHI	UPLIFT	FS
•	1944	880	31		2.38
•	1946	0	31		1.40
•	1973	600	30		1.39
•	1979	1200	50		2.16
•	1983	0	39.3	100%	0.88
•	1983	0	39.3	50%	1.2
•	1997	0	33	100%	0.7
•	1999	0	25	100%	0.55
•	1999	0	25	50%	0.88
•	2004	0	25	100%	0.50

One Corps Serving The Army and the Nation



US Army Corps
of Engineers


CANTON DAM SPILLWAY STABILITY



One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM SPILLWAY STABILITY


- **Determining Anchor Capacity**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR DESIGN LOAD FORMULA



$$P = \tau_w * L_b * \pi * d$$

P = design load for the anchor

τ_w = working bond stress along the interface
between rock and grout


τ_w = 50% of the ultimate bond stress

L_b = bond zone length

d = diameter of drill hole



US Army Corps
of Engineers



RECOMMENDED BOND STRESS VALUES FROM PTI

ROCK	AVERAGE ULTIMATE BOND STRESS-ROCK/GROUT (PSI)
Granite and Basalt	250 – 450
Dolomitic Limestone	200 – 300
Soft Limestone	150 – 200
Slates & Hard Shales	120 – 200
Soft Shales	30 – 120
Sandstones	120 – 250
Weathered Sandstones	100 – 120
Chalk	30 – 155
Weathered Marl	25 – 35
Concrete	200 – 400



Table 6.1, Recommendations for Prestressed Rock and Soil Anchors, PTI, 1996

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I CORE STRENGTHS



Minimum = 120 psi

Maximum = 1,040 psi

One Third = 330 psi


Median = 420 psi

Average = 456 psi


One Corps Serving The Army and the Nation



US Army Corps
of Engineers



TEST ANCHOR PROGRAM PHASE II CORE STRENGTHS



Minimum = 50 psi

Maximum = 860 psi

One Third = 300 psi

Median = 440 psi


Average = 460 psi

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I & II SUMMARY



- **Ultimate Bond Stress = 10% of the Unconfined Compressive Strength of the Rock**
- **Minimum Value = 5 to 12 psi**
- **One Third Value = 30 to 33 psi**
- **Median Value = 42 to 44 psi**
- **Average Value = 46 psi**
- **Maximum Value = 86 to 104 psi**


One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM

LAB BOND TESTS



Boring	Maximum Bond Stress (psi)	Boring	Maximum Bond Stress (psi)
BL-1	102	BR-4	104
BL-1	57	BR-4	233
BL-2	81	BR-5	176
BL-2	84	BR-5	62
BL-2	141	BR-6	154
BL-3	98	BR-6	65
BL-3	76	BR-6	300

Minimum = 57 psi

Maximum = 300 psi

One Third = 80 psi

Median = 100 psi

Average = 109 psi


One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM

PHASE I PULLOUT TESTS




Boring	Bond Zone Length (ft)	No. of Strands	Percent of Design Load (%)	Bond Stress (psi)
A-1LA	15	7	118	63
A-1RA	15	7	165	97
A-3L	15	7	160	94
A-3R	15	7	155	91
A-2L	15	16	188	221
A-2R	15	16	190	224
A-5L	15	16	188	221
A-5R	15	16	190	224
A-4L	40	16	133	83
A-4R	40	16	133	83

No anchors failed during pullout tests

One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM SPILLWAY STABILITY


- Investigation and Test Anchor Program

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

INVESTIGATION AND TEST PROGRAM




- **Two phase test program required due to lack of funding**
- **Phase I – abutment drilling**
 - 6 core holes
 - 8 anchor pullout tests
 - 2 anchor creep tests
- **Phase II – spillway drilling**
 - 4 core holes
 - 2 full scale anchor tests
- **Awarded task orders for investigations and test anchors to MACTEC (Prime) and Hayward Baker (Sub)**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I




- **3 core holes on each side of the spillway**
 - 2 to 140 feet
 - 1 to 180 feet (top of gypsum)
- **2 test anchors on each side of spillway**
 - 105 and 140 feet deep
 - 6 inch diameter hole
 - 7 strand tendon instrumentation
 - 15 foot bond zone
 - Perform pullout test to failure
 - Could not fail anchors

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I - INVESTIGATION



One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I - INVESTIGATION



One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I - INVESTIGATION




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I - INVESTIGATION



FINDINGS


- Original boring logs indicated caved material
- Caved material turned out to be the result of dissolution and collapse
- Noticeable increase in core recovery, RQD, and strength of core below 90 feet
- Rock dips slightly to the southwest

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I





One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED




- **2 test anchors on each side of spillway**
 - 105 feet deep (one grouted and one not grouted)
 - 6 inch diameter hole
 - 16 strand tendon
 - 15 foot bond zone
 - Perform pullout test to failure
- **2 test anchor on each side of spillway**
 - 105 feet deep
 - 6 inch diameter hole
 - 16 strand tendon with instrumentation
 - 40 foot bond zone
 - Conduct performance test and creep test

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED





One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED






One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED





One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED




One Corps Serving The Army and the Nation




US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED



Canton Dam, A4 Left Load Test - Load Per Depth in Bond Zone





Tensmeg Strain Gage ID and Depth from Top of
Bond Zone

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I REVISED




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE II




- **Core 4 investigation holes in spillway to an elevation of 1460**
 - Collect and test samples for strength and consolidation
- **2 production anchors at gate 16 in existing spillway**
 - One 32 strand anchor drilled at 18.4° to elevation 1470
 - One 28 strand anchor drilled at 30.0° to elevation 1470
 - 12 inch diameter hole
 - 40 foot bond zone
 - Conduct performance test and creep test

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INVESTIGATION PHASE II



One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INVESTIGATION PHASE II




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II



One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II




One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II FINDINGS




- **Weir access is difficult**
 - Slick surface
 - Tight workspace
 - Load limit on spillway bridge
- **Continuous flow of cuttings is required**
 - Falling cuttings blocked hole and drill tools
- **Hole will cave in 12 to 24 hours**
 - Duplex type casing would be ideal but none exists for this size of hole
- **Control elongation of corrugated pipe**
- **Drill one hole and install corrugated pipe in that hole before starting another one**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

ANCHOR INSTALLATION PHASE II FINDINGS




- **Stage grout to avoid buckling corrugated pipe**
- **Measure top of grout accurately to avoid clogging of other grout tubes**
- **Consider single stage vs. two stage grouting**
- **Label grout and flush tube adequately**



One Corps Serving The Army and the Nation



US Army Corps
of Engineers




ANCHOR DESIGN



One Corps Serving The Army and the Nation



US Army Corps
of Engineers



CANTON DAM SPILLWAY STABILITY

- **Summary**

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM SUMMARY




- **Ultimate Bond Stress Values**
 - From PTI Table = 30 to 120 psi
 - From Unconfined Compressive Strength Tests = 30 to 45 psi
 - From Lab Bond Tests = 80 to 110 psi
 - From Pullout Tests = 100 to 220 psi
 - No anchors failed during pullout test
 - Full scale anchor tests loaded to 133% of design load = 83 psi working bond stress

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM SUMMARY




- **Total force required for weir section = 1,550 kips**
 - 12 anchors would be required for an ultimate bond stress of 30 psi
 - 2 anchors are be required for an ultimate bond stress of 120 psi
- **Total force required for pier section = 1,830 kips**
 - 14 anchors would be required for an ultimate bond stress of 30 psi
 - 2 anchors are be required for an ultimate bond stress of 120 psi

One Corps Serving The Army and the Nation



US Army Corps
of Engineers

TEST ANCHOR PROGRAM PHASE I & II SUMMARY



- **Phase I**
 - Cost approximately \$700,000
 - Reduced the number of anchors from over 400 to 112
 - Cost savings of over \$6,000,000
- **Phase II**
 - Cost approximately \$800,000
 - Reduced the number of anchors from over 112 to 64
 - Cost savings of over \$2,000,000
- **Total cost of \$1,500,000**
- **Total savings over \$8,000,000**
- **Return on the investment of more than 5 to 1**


One Corps Serving The Army and the Nation



US Army Corps
of Engineers

SPILLWAY STABILITY

CANTON LAKE



Is a Test Anchor Program Necessary?

It certainly was for us

Some considerations if you are thinking about a test program


- Consider the total load required per monolith
- Consider the type of rock
- Consider the configuration of the structure



US Army Corps
of Engineers

SPILLWAY STABILITY

CANTON LAKE



Dam Safety Assurance Project Is a Test Anchor Program Necessary?

One Corps Serving The Army and the Nation



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Marmet Lock & Dam

Automated Instrumentation Assessment

Summer / Fall 2004

2005 Tri-Service Infrastructure Conference
August 4, 2005

Jeff Rakes 304-399-5809

Ron Adams, P.G. 304-949-1934



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Considerations

- ◆ Project Overview
- ◆ Automated Data Acquisition System Overview
- ◆ ADAS Challenges
- ◆ Deep Seated Sliding Occurs
- ◆ ADAS Failure
- ◆ Emergency Action Plan Response
- ◆ Remediation Attempts
- ◆ Current Status



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team


Project Overview

- ◆ Project Located On Kanawha River
(Just SE Of Charleston, WV)
- ◆ Built In 1934 – Twin Locks 56'x360'
- ◆ Average Lock Time Is Over 4 Hours Per Tow
- ◆ Contract Awarded May 2002
 - Kokosing / Frucon, LLC (KFC)
- ◆ Estimated 7-year Construction
- ◆ New Lock Is 110'x800'



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team



Project Location



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team




Marmet Lock & Dam Prior to New Lock Construction




US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team



Marmet Lock - New Construction





Cofferdam at Time of Initial Movement



Cofferdam at Time of Initial Movement



Cofferdam at Time of Initial Movement



08/19/2004
Cofferdam at Time of Initial Movement



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview

- ◆ Monitors Cofferdam Cells, Existing Lock Wall And Spoil Site
- ◆ Central Monitoring Station
- ◆ Geo-Net / Geo-View Website Computers
- ◆ 30 Remote Computers (MCU)
(Measurement And Control Unit)
- ◆ 350+ Sensors Include:
 - IPI (In-Place Inclinometers)
 - Vibrating Wire Piezometers
 - Load Cells (On Anchors)
 - Digital Tilt Meters
 - Pool Transducers



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview

Manually Read Instruments

- ◆ Portable Inclinometers
- ◆ Settlement And Alignment Pins
- ◆ Joint Monitoring Pins
- ◆ Saw Cuts



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview




30 MCUs (Remote Computers)
Installed on Site



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview



MCU Locations (Shown in Red)



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview

Cofferdam Cell Installations



Upstream Cells



Downstream Cells



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview

Lock Wall Installations





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview

Load Cells On Anchors





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Overview





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Challenges

◆ Grounding / Physical Location

- MCUs Located On Cells And Existing Lock Wall
 - Kanawha River On West Side
 - Excavated Walls / Construction On East Side
 - No Good Location For Individual Grounds
 - Bare Copper Ground Wire Runs From Upstream Cell To Downstream Cell, Exposed Above Ground
 - Copper Ground Wire Fastened To Safety Fence
 - All Lock Wall MCUs Grounded To Same Copper Ground Wire



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Challenges Grounding / Physical Location





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Challenges Grounding / Physical Location





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Challenges

- ◆ Communication Antenna Arrays
 - Two Large Communication Arrays Are Located Within 2-miles Upstream And Downstream Of Marmet Lock
 - The Arrays Both Transmit And Receive Signals Over A Wide Range Of Frequencies
- ◆ River Traffic Radio Transmissions
 - Lock To Barge Communications
- ◆ Hydroelectric Plant Control
 - Remote Communication Control
- ◆ All Data Transmission Is Performed Via Radio Between The MCUs And The Central Monitoring Station



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Challenges

◆ Limited On-site Expertise

- Hardware And Software Support Is Provided By Off-site Sub-contractors

◆ Limited Experience With MCU / Software

- Initial Installer And Programmer Had Limited Experience With Geomatics Hardware / Software



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Deep Seated Sliding Occurs

◆ Construction Status At The Time Movement Occurs

- All Rock Anchors And Thrust Blocks Had Been Installed
- Drilling, Rock Blasting And Foundation Rock Excavation Had Begun In Downstream Area Of Cofferdam
- Reading, Plotting And Evaluation Of Instrumentation Data Was An Ongoing Task



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Deep Seated Sliding Occurs

◆ Initial Downstream Movement


- August 2004 Movement Occurred Along Two Weak Planes
 - El 540 +/- Where There Is A Series Of Thin Seams Of Carbonaceous Shale And Coal Within An Otherwise Generally Competent Sandstone Formation
 - El 520 +/- Where There Is A Discontinuous Thin Seam Of Clayey Material Near The Bottom Of The Sandstone Unit And An Underlying Shale Formation. This Seam Is Slightly Lower Than Any Required Excavation



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Deep Seated Sliding Occurs




Cofferdam Area



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Deep Seated Sliding Occurs





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Deep Seated Sliding Occurs

◆ Initial Downstream Movement - Continued

- The Magnitude Of The Movement Was Consistent With That Expected For The Initial Transfer Of Load As Estimated From Direct Shear Tests In The Foundation Rock
- The Movement Was Generally Within Tolerable Limits; However The Consensus Of The PDT Was That The Trend Of Gradual And Steady Increases Warranted Concern And Additional Scrutiny



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Deep Seated Sliding Occurs

◆ Initial Downstream Movement - Continued

- The Movement Stabilized Within 6-8 Weeks After Rock Blasting And Foundation Rock Excavation
- The Initial Threshold Of 0.25" Of Total Movement Was Revisited By The PDT And Deemed Reasonable And Appropriate.

◆ Additional Upstream Movement


- Additional Upstream Movement Was Anticipated And Did Occur, But PDT Response Actions Minimized The Magnitude Of That Movement.



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Total Movement To Date





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Failure

- ◆ Reliability Of The ADAS Had Been Suspect For Some Time
 - Significant Disagreements Between IPI And Portable Inclinator Readings
 - IPI Readings Had Provided Erratic Results
 - Excessive Number Of False Alarms
 - Monthly Instrumentation Reports Regularly Contained Graphs With Considerable Gaps In Recorded Data And Readings That Significantly Exceeded Established Threshold Limits



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team



ADAS Failure

◆ August 31, 2004 Special Meeting

- Contractor Provides COE With Portable Inclinator Graphs Indicating Movement In Foundation Below Several Monoliths And Cells
- Movement Elevations Correlated With Previously Identified Weak Seams And Occurred In Four Consecutive Weekly Readings
- Movement Was Recorded In Graphs For A Number Of Adjacent Cells And Monoliths
- Movement Was Oriented Landward And Occurred A Few Weeks After Blasting And Excavation Of Adjacent Foundation Rock Had Begun
- Rate Of Movement Was Consistent And Linear (0.01" To 0.02" Per Week)







One Corps, One Regiment, One Team



Initial Movement – Cell 2D
August 2004




One Corps, One Regiment, One Team



Initial Movement – Cell 6D
August 2004




One Corps, One Regiment, One Team





One Corps, One Regiment, One Team

MARMET 6D-P, A-Axis





US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

ADAS Failure

◆ Resulting Actions

- The Readings Recorded By The ADAS Did Not Correlate With The Movement Identified By The Portable Inclinator Surveys And Validated COE Concerns
- The Lack Of Confidence In The ADAS Resulted In An Increase In The Number And Frequency Of Portable Inclinator Readings And Resulting Evaluation Of That Data
- COE Directed The Contractor To Perform An Investigation Of The ADAS
- While Some Movement Was Expected, The PDT Developed An “Emergency Action Plan” To Provide Guidance If The Movement Exceeded Anticipated Levels



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

E.A.P. Response

Engineering & Construction Division Response

Movements in Rock Foundation
Marmet Construction Project

17 September 2004
Updated 27 September 2004
Updated 30 September 2004

Developed from PDT and Management Meetings
September 2004

Outline

1. Purpose
2. Background Information
3. Site Observations
4. Conclusions
5. Recommendations



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

E.A.P. Response

◆ Recommended Actions Of The PDT

- Increase Frequency Of Instrumentation Readings And Evaluation Of Data
- Reanalyze Additional Failure Planes Within The Rock Foundation
- Complete Second Stage Grouting Of Anchors
- Add Additional Upstream Anchors
- Add Additional Inclinometers Of Greater Depth And At Additional Locations
- Improve Reliability Of Instrumentation System



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

E.A.P. Response

◆ Recommended Actions Of The PDT – Continued

- Obtain Additional Technical Oversight (Engineering Geology Experts, RTS, Etc)
(Instrumentation Experts)
- Evaluate Alarm Thresholds For Load Cells
- Establish Displacement Thresholds And Stabilizing Actions



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Remediation Attempts

◆ Instrumentation Summit #1 (Sept 2004)

- Remote Computers
 - Contractor Recommended System Change From Geomation To Campbell
- In-Place Inclinometers
 - Thermal Drift



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Remediation Attempts

◆ Instrumentation Summit #2 (Nov 2004)

- Remote Computers
 - Replace All Remaining Original Boards
 - Upgrade Charging System
 - Reprogram Recanvassing Frequency
 - Possible Signal Interference
- In-Place Inclinometers
 - Thermal Drift
 - Install IPIs With Automatic Compensation
 - Develop Programming Compensation For IPIs Currently Installed Without Compensation Capability
- Install Load Cells On All New Anchors



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Remediation Attempts

- ◆ Geomation 2380MCU Performance History Review / Research (March 2005)
 - CELRH Conducted Performance Evaluation of 2380MCU To Determine If Unit Has Been Utilized With Success In Similar Applications.
 - Review Included Published Reports And Papers, Discussions With System Integrators And Actual End Users.
 - Review Answered Reliability Issue In The Affirmative



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Remediation Attempts

◆ Instrumentation Summit #3 (April 2005)

- Reprogram Recanvassing Frequency
 - Increase Time Of Alarm Confirmation Readings
 - Alarms Now Triggered By Two Consecutive Readings That Exceed Threshold Limits As Opposed To One
- Install Older Version Of Firmware On Specific MCUs
- MCU Isolation Tests
 - From Radio (Airborne Transients)
 - From Cabled Instruments (Subsurface Transients)
- Tilt Meters
 - Excitation Voltage No Longer Provided By MCU



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Remediation Attempts

◆ Instrumentation Summit #3 (April 2005) – Cont.

- In-Place Inclinometers
 - Recalibrate Thermal Compensation
 - Excitation Voltage No Longer Provided By MCU
- Campbell System Test Installation
- Website
 - Update To Include All System Modifications
 - Address Issue Of Lost Data Transmission



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Remediation Attempts

◆ TCX - APMD

- Technical Center of Expertise (TCX) for Automated Performance Monitoring of Dams (CEMVS) has been contracted to perform an independent evaluation of the Marmet ADAS through a contract with URS



US Army Corps
of Engineers
Huntington District

One Corps, One Regiment, One Team

Current Status of ADAS

◆ Reliability Of Data Still Suspect

- Contractor has been able to reduce the number of false alarms but the reliability of data being produced is still suspect.

◆ TCX – APMD / URS

- On Site System Review Week Of 15 August



One Corps, One Regiment, One Team

Jeff Rakes
304-399-5809

Ron Adams, P.G.
304-949-1934



BEARS

Questions ?



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM


Mississinewa Dam Foundation Rehabilitation

Jeff Schaefer

Geotechnical Regional Technical Specialist

U.S. Army Corps of Engineers

Louisville District






**US Army Corps
of Engineers**
Louisville District

CIVIL WORKS PROJECTS



VICINITY MAP





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM



Constructed – Mid to Late 1960's

- Total length 8100 feet
- Total height 140 feet
- Crest elevation 797
- Spillway elevation 779
- Summer Pool 737 *
- Winter Pool 712



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Geology

Glacial Deposits: 10-70 feet Silty clay overlying
sands and gravels


Liston Creek Fm: 0-70 feet Thinly bedded, cherty,
crystalline limestone
prone to solutioning.

Mississinewa Fm: > 30 feet Thinly bedded
argillaceous limestone



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM




Typical geologic cross-section along the dam centerline.


Voids

**Damaged
Instrumentation**

Open Joints



**Highly
Fractured**



**24-foot
Solution
Feature**

**Clay Filled
Features**



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM




Figure 3. --Block diagram showing the structure of lapies and grikes.

Adapted From Indiana Geological Survey,
Caves of Indiana by Richard L. Powell



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Solution feature
on left abutment
side of conduit
excavation





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**




View of solution
channel, located at
dam station 51+00,
on left abutment side
of conduit excavation.



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM






**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Features of Interest for the Mississinewa Dam Project






**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**


1988

Operations Personnel Identify
Guardrail Deflections

Change In Elevation From Original Elevation



Change In Elevation From Original Elevation



Sep-70	Oct-70	Nov-70	Dec-70	Jan-71	Feb-71	Mar-71	Apr-71	May-71	Jun-71	Jul-71	Sep-71
Mar-72	Mar-73	Aug-73	Mar-74	Sep-74	Sep-76	Aug-78	Mar-79	Jun-79	Dec-79	Mar-80	Jun-80
Sep-80	Dec-80	Mar-81	Jun-81	Dec-81	Jun-82	Dec-82	Mar-83	Jun-83	Dec-83	Jun-84	Dec-84
Jul-85	Mar-86	Mar-87	Sep-88	Mar-89	May-90	Aug-91	May-92	Feb-93	Oct-93	Mar-94	Jun-94
Jun-95	Sep-95	Oct-96	Feb-98	Oct-98	Feb-99	Jun-99	Aug-99	Jan-00	Jun-00		




**US Army Corps
of Engineers**
Louisville District


Geotechnical and Dam Safety Section
MISSISSINEWA DAM

SI-1 (station 40+25),
approximately elevation 758

View in May 1995




View in June 1999





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**




June 1999 view of SI-2 (station 40+25)
at approximately elevation 758



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Settlement Mechanism Foundation Piping



Not To Scale



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**


Cut-off Wall

A cut-off wall was selected as the only practical and certain method of repairing the foundation for the dam. The cutoff wall would extend to depths of 180 feet and up to 80' into rock.



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM



Typical geologic cross-section along the dam centerline.



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Construction Contract

RFP Performance Specification

Requirements Specified & Methods Restricted

Methods Selected by Contractor

Technical Factors More Important Than Price



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Contract Award


All 3 Proposed Clamshell/ Hydrofraise
Backup Method – Chisel Supplement

Award to Bencor/Petrifond JV
for \$29,800,000 September 2000



**US Army Corps
of Engineers**
Louisville District


**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Site Map Showing Major Areas of Interest





**US Army Corps
of Engineers**
Louisville District


Geotechnical and Dam Safety Section MISSISSINEWA DAM





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM





US Army Corps
of Engineers
Louis

Cable-Clam Bucket


Geotechnical and Dam Safety Section
MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**






US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Test Section



Typical geologic cross-section along the dam centerline.



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Test Section

Attempts to Excavate Rock in Test
Section Resulted in Sudden Complete
Slurry Loss



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Test Section

Change To Construction Approach

Pregrouting Required to Enable Cutoff Wall
Construction

RFP type selection of the Grouting Subcontractor
(ACT)

Grouting ITR by Dr. Donald Bruce



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



Rotosonic Drill Rig



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



Sample Extrusion



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



Rotosonic Samples



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



Rock Drill



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



Two High Speed/High Volume Grout Plants



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



Grout Header Controls



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**



IntelliGrout



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**




IntelliGrout Operator's Station



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM




Typical Void Refusal, Refined “D Mix”



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM


Test Section





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**




B Line Master Drawing



US Army Corps
of Engineers
Louisville District

Grout Line Layout

Geotechnical and Dam Safety Section
MISSISSINEWA DAM



Downstream

Upstream



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Tremie Concrete Placement





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Test Section

Test section is complete.

Pregrouting was successful. NO SLURRY LOSSES

An optimum program for production was developed.

Drilling for grouting will provide a preview to problems.

Cost growth due to grouting is unknown.

Actual quantities required to treat features will govern.

\$10 - 15 Million (Likely)


\$25 Million (Worst Case)



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Production Grout Hole Alignment



Holes were drilled on both sides of the cutoff wall



US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Crane Mod For Deep Section



Bencor-Petrifond, J.V.



Extended Hydromill
June, 2004

Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Crane Boom Failure





**US Army Corps
of Engineers**
Louisville District

Crane Fire

Geotechnical and Dam Safety Section
MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Mill Recovery



Bencor-Petrifond, J.V.



Mill Retrieval With Dywidag Bars
September, 2004

Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Mill Recovery



Bencor-Petrifond, J.V.



Mill Retrieval Hydraulic Jacks
September, 2004
Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Mill Recovery



Bencor-Petrifond, J.V.



Mill Removal From Panel P-121
September, 2004
Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Mill Recovery





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Additional Mills Mobilized



Bencor-Petrifond, J.V.



Sennebogen Rig #2 Rock Excavation
October, 2004

Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Soil Cutting Wheels



Bencor-Petrifond, J.V.



Hydromill Soil Wheels

December, 2004

Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

Mill Fest



Bencor-Petrifond, J.V.



Hydromills On Platform
December, 2004
Dam Foundation Remediation
Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers






US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Final Wall Profile





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Quality Control

- Bentonite Testing
- Panel Embedment & Continuity
- Panel Verticality
- Concrete Testing
- Verification Drilling
- Dam Instrumentation



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Bentonite Testing Equipment



Mud Balance and Marsh Funnel Cone



Pressure Filtration Machine



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Marsh Funnel Test





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Density Test





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section

MISSISSINEWA DAM

Pressure Filtration Testing





US Army Corps
of Engineers
Louisville District

Sand Content Testing

Geotechnical and Dam Safety Section
MISSISSINEWA DAM





**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Cuttings Observations for Panel Embedment





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Verticality Checks


- Hydromill Inclinator
- Jean Lutz® Inclinator/Gyroscope
- Plumb Bob
- Koden® 682/684



US Army Corps
of Engineers
Louisville District

Jean Lutz® Plot

Geotechnical and Dam Safety Section
MISSISSINEWA DAM





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Koden® Verticality Machine








US Army Corps
of Engineers
Louisville District

Koden® Plot

Geotechnical and Dam Safety Section
MISSISSINEWA DAM






US Army Corps

Plumb Bob Reading

Geotechnical and Dam Safety Section
MISSISSINEWA DAM



CRANE





US Army Corps
of Engineers
Louisville District

Plumb Bob Results

Geotechnical and Dam Safety Section
MISSISSINEWA DAM




Bencor-Petriford, JV
Dam Foundation Remediation, Mississinewa Dam
18-Aug-03

Panel P-11 - Bite #1 - Verticality - Plumb Bob			
Height of Boom = 46'	Depth (Ft.) Below Guide Wall	Readings at Guide Wall (Inches)	Panel Deviation (Inches)
	0.00	0.00	0.00
	20.00	0.00	0.00
	30.00	0.13	0.21
	40.00	0.13	0.23
	50.00	0.38	0.78
	60.00	0.38	0.86
	70.00	0.20	0.60
	80.00	0.20	0.55
	90.00	0.63	1.85
	100.00	0.63	1.98
	110.00	1.00	3.39
	120.00	1.00	3.61
	130.00	1.00	3.83
	140.00	1.00	4.04
	150.00	1.13	4.79

Panel P-11 - Bite #2 - Verticality - Plumb Bob			
Height of Boom = 35'	Depth (Ft.) Below Guide Wall	Readings at Guide Wall (Inches)	Panel Deviation (Inches)
	0.00	0.00	0.00
	20.00	0.00	0.00
	30.00	0.25	0.46
	40.00	0.63	1.34
	50.00	1.00	2.43
	60.00	1.25	3.39
	70.00	1.38	4.13
	80.00	1.50	4.93
	90.00	1.63	5.80
	100.00	1.75	6.75
	110.00	2.13	8.80
	120.00	2.50	11.07
	130.00	2.13	10.02
	140.00	2.00	10.00
	150.00	1.50	7.93

Panel P-11 - Bite #3 - Verticality - Plumb Bob			
Height of Boom = 20'	Depth (Ft.) Below Guide Wall	Readings at Guide Wall (Inches)	Panel Deviation (Inches)
	0.00	0.00	0.00
	20.00	0.00	0.00
	30.00	0.25	0.51
	40.00	0.38	0.89
	50.00	0.75	2.04
	60.00	1.00	3.07
	70.00	1.00	3.41
	80.00	1.00	3.76
	90.00	1.00	4.10
	100.00	0.88	3.89
	110.00	0.88	4.19
	120.00	0.88	4.50
	130.00	0.75	4.11
	140.00	0.75	4.37
	150.00	0.75	4.63

Note: (-) Upstream, (+) Downstream





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Concrete Quality Checks

- Batch Plant
 - Scale Calibration quarterly
 - Electronic Moisture meter calibration
 - Sieve Analysis on aggregates
 - Gradation analysis on aggregates
 - Moisture on sand and aggregate
 - Fly-ash grain size analysis




US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Tremie Procedures

- Go-Devil utilized
- Tremie Pipe Embedment
- Chart tremie progress and quantities
 - (in real time)
- Count tremie pipe lengths





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Concrete Quality Testing

During Placement--

- Slump
- Air Content
- Temperature





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Verification Drilling

- Purposes:
 - Concrete Quality
 - Panel Contact/Joint Quality
 - Cutoff-Wall---Rock Bottom Contact
- Techniques:
 - 4 inch core for Panels
 - 6 inch core for Panel Joints



Bencor-Petrifond, J.V.



Concrete Verification Drill Rig

January, 2005

Dam Foundation Remediation

Contract No. DACW27-01-C-0018

U.S. Army Corps of Engineers





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Verification Drilling







US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Panel-Rock Contact



What we don't want!






US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Borehole Pressure Testing



- Verifies wall water-tightness
- Verifies Wall-Rock Interface




US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Dam Instrumentation

- Purposes
 - Verify dam integrity
 - Check effectiveness of grouting
 - Check effectiveness of concrete cutoff wall
 - Historical record for future use

Paired Piezometers






US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

Paired Piezometer Plot

PZ-108 Up vs Down (station 39+05)--Mississinewa Project History





US Army Corps
of Engineers
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM

What have we learned?

- Solution Features are worse than expected.
- Clearly we were in a failure mode, reinforcing the need for remediation.
- Need for Pool restriction reinforced.
- Pregrouting is required to control slurry loss.
- Need to adjust design to field conditions.
- Cost and Schedule Growth will be governed by Geology.
- Large Contingencies are required for foundation repair projects.



**US Army Corps
of Engineers**
Louisville District

**Geotechnical and Dam Safety Section
MISSISSINEWA DAM**

- Final Price Approx. \$50 Million.
- Most of the cost growth due to pretreatment grouting.
- No milling production issues related to rock strength.



**US Army Corps
of Engineers**
Louisville District

Geotechnical and Dam Safety Section
MISSISSINEWA DAM





An Overview of the Dam Safety Program Management Tools (DSPMT)

2005 USACE Infrastructure Conference
3 August, 2005



Objective


- To provide an overview of why this program is needed, what it is and how it is being utilized.

Why is this Software Needed?


- To Support Broad Information Needs of the National Dam Safety Program, including:
 - Documenting the characteristics and condition of the Nation's dams
 - Tracking the existence and progress of dam safety programs
 - Supporting dam safety professionals who are responsible for evaluating and maintaining the safety of dams in the U.S.

Specifically, the DSPMT:

- Allows quantitative, consistent, un-biased evaluation of dam safety programs
- Monitors program progress
- Consistent interface
- Allows exchange of data with other databases
- Simplifies data collection process allowing true One-time data entry to be possible
- Program Review Tool




What is the DSPMT ?



- Free Software for States or Federal Agencies
- Desktop-based Software that keeps the User in control of the data
- Benefits:
 - DSPMT Utilization will reduce/eliminate requests for data because the requesting organization can go directly to the data itself
 - Can result in significant time savings for generating:
 - Annual NDSRB State Evaluation Criteria Reports
 - Peer Review Data
 - NID Submittals
 - NPDP Incident Reports
 - Inputs for Biennial Report to FEMA
 - Unbiased data for self-evaluation or evaluation by others

DSPMT Components



- ◆ **Dam Safety Program Performance Measures (DSPPM)**



- ◆ **National Inventory of Dams (NID) Electronic Submittal Workflow**



- ◆ **Reporting Capabilities to National Oversight Organizations**




DSPMT

Why do we need dam safety program performance measures?


- *They provide the raw unbiased data necessary for helping to evaluate our dam safety programs, for reporting our accomplishments, and for expressing our program needs to others.*

What are the Dam Safety Program Performance Measures?




- **DSPPM 1 - Dam Safety Program Legislative Authorities & Management Practices**
 - Demonstrates: Adoption **and** implementation of uniform National Dam Safety Program management practices.
- **DSPPM 2 - Dam Safety Staff Size & Relevant Experience**
 - Demonstrates: The trends & fluctuations in an organization's dam safety staff size and relevant experience.
- **DSPPM 3 - Inspections & Evaluations**
 - Demonstrates: Number of dams and the number that **are** and **are not** being inspected & evaluated.
- **DSPPM 4 - Identification & Remediation of Deficient Dams**
 - Demonstrates: Dam Safety program effectiveness in **identifying, prioritizing** and **correcting** critical deficiencies.

What are the Dam Safety Program Performance Measures?




- **DSPPM 5 - Project Response Preparedness**
 - Demonstrates: Amount of dam safety **training** aimed at maintaining capability to **recognize & respond** to conditions that may threaten dam safety & public safety.
 - Demonstrates: Extent of up-to-date project (dam) **documentation** (e.g. as-builts).
- **DSPPM 6 - Agency & Public Response Preparedness**
 - Demonstrates: Extent of agency and public (local) emergency **awareness & preparedness**.
 - Demonstrates: Effectiveness in **development** of EAP's & **coordinating** EAP's with local jurisdictions.
- **DSPPM 7 - Unscheduled Dam Safety Program Actions**
 - Demonstrates: Magnitude of unscheduled, non-deferrable **efforts** and **incidents** that adversely impact routine program execution.

DSPPM 7 will be Expanded very soon to Include:



- **Capability for Notification of Distress in Civil Works Structures to Hq including information such as the following:**
 - Date of incident
 - Date of site visit
 - Category/ reason for site visit
 - Did the dam fail? (current)
 - Failure type
 - Failure mode
 - Was the dam previously identified as being deficient? (current)
 - Was the actual failure mode previously identified as a deficiency? (current)
 - Were emergency remedial actions necessary?
 - Were pool restrictions imposed?
 - Etc.

The Performance Measures are implemented using detailed spreadsheets



Full DSPPM Spreadsheet

Click on a cell to select it. Type into the cell to change the value. Double-click on a cell to cycle through possible values.

Dam Name (32 Dams)	NIDID	Owner Name	Last Inspection Date	Inspection Type	Inspection Performed by	Date Permit Application Rcvd
BALDHILL	ND00309	CEMVP	07/30/2003	Comprehensive	In-House	N/A
BROWN S VALLEY	MN82201	CEMVP	07/27/2004	Comprehensive	In-House	N/A
CHIPPEWA DIVERSION DAM	MN00578	CEMVP	08/06/2002	Comprehensive	In-House	N/A
EAU GALLE	WI00780	CEMVP	09/13/2000	Comprehensive	In-House	N/A
GULL LAKE	MN00596	CEMVP	07/28/2003	Comprehensive	In-House	N/A
HIGHWAY 75 DAM	MN00581	CEMVP	07/28/2003	Comprehensive	In-House	N/A
HOMME DAM	ND00310	CEMVP	07/28/2003	Comprehensive	In-House	N/A
LAC QUI PARLE DAM	MN00580	CEMVP	07/28/2003	Comprehensive	In-House	N/A
LEECH LAKE DAM	MN00585	CEMVP	07/28/2003	Comprehensive	In-House	N/A
LOCK & DAM #1	MN00593	CEMVP - FORD	07/28/2003	Comprehensive	In-House	N/A
LOCK & DAM #10	IA00001	CEMVP	07/28/2003	Comprehensive	In-House	N/A
LOCK & DAM #2	MN00594	CEMVP - CITY OF	09/12/2001	Comprehensive	In-House	N/A
LOCK & DAM #3	MN00595	CEMVP	09/11/2001	Comprehensive	In-House	N/A
LOCK & DAM #4	WI00727	CEMVP	09/12/2002	Comprehensive	In-House	N/A
LOCK & DAM #5	MN00589	CEMVP	09/11/2002	Comprehensive	In-House	N/A
LOCK & DAM #5A	MN00588	CEMVP	09/10/2002	Comprehensive	In-House	N/A
LOCK & DAM #6	WI00802	CEMVP	09/11/2003	Comprehensive	In-House	N/A
LOCK & DAM #7	MN00587	CEMVP	09/10/2003	Comprehensive	In-House	N/A

Select Cell for Modification.

(1) Set Performance Measure Default Values Show DSPPM Completion Status

(2) Initialize Blank Fields Export to Excel

Show Deficiencies Spreadsheet for:


Sort By:

Screen 33

The performance measure spreadsheet shows All of the performance measure fields as Columns and all of the projects as rows.

Specifically, the Performance Measure Spreadsheet is used for:

- Supporting generation of the biennial report to FEMA
 - Number of Dams
 - Hazard Potential Classification Information
 - Inspection Information
 - Remediation Needs and Accomplishments
 - Emergency Action Planning Performance
- Supporting general data requests from both within and external to the Agency



The Staffing Details Spreadsheet

Dam Safety Staffing Details Spreadsheet

Click on a cell to select it. Type into the cell to change the value. Double-click on a cell to cycle through possible values. Press <Enter> to store the value. After selecting a cell, Press F1 for an explanation of that field.

Name/Number (24 Persons)	Organization	Specialty	Years Dam Safety Experience	Estimated Years to Retirement	Number of Comprehensive (PI) Inspections
Travis Adams	CENWP	Structural Engineer	8	25	
Teresa Morales	CENWP	Structural Engineer	1	30	
Jeff Hurt	CENWP	Structural Engineer	10	25	
Jeff Arment	CENWP				
David Kloewer	CENWP				
Tom North	CENWP				
Arthur Fong	CENWP				
Laurie L Ebner	CENWP				
Doug Richards	CENWP				
Carolyn Flaherty	CENWP				
James B. Griffiths	CENWP				
Jeremy Britton	CENWP				
Matthew Hanson	CENWP				
Kristie Hartfeil	CENWP				
Joseph Bracklin	CENWP				
Lois Miller	CENWP				

Done

☐ Allow Changes to Staff Person's Name

Add New Staff Person

Min->Max
Max->Min

Sort Rows

Modify Selected Field Value

Comment

Delete Selected Staff Person

Print All Records

Print Selected Record

Export to Excel

Exit

Screen 10.5


?

- The staffing details spreadsheet includes:
 - Name/Number
 - Organization
 - Specialty
 - Years Dam Safety Experience
 - # Comprehensive (PI) inspections in career
 - Supervisor/Team Leader/Program Manager?
 - # Projects having a major role in design or construction
 - Normal duties (Engineering Construction or Operations)
 - Registered Professional?, Type of registration
 - Degree Year, Level, Type
 - % Time dedicated to dam safety program

Specifically, the Staffing Details Spreadsheet can be used for:

- Evaluating the number of FTE's
- Evaluating an Organization's capability to execute the dam safety program
- Supporting generation of the draft biennial report to FEMA
 - Number of FTE's (i.e. Staff multiplied by % of time dedicated to dam safety)
 - Specialty category (i.e. Geotechnical Engineer, Structural Engineer, etc.)

The Deficiencies Spreadsheet



Deficiency Spreadsheet

Dam: BALDHILL

(After Selecting a cell, Press F1 for an explanation of that field)

Click on a cell to select it. Type into the cell to change the value. Double-click on a cell to cycle through possible values.

Project Name	Organization/ Agency/ State	Deficiency Category	Description	District Priority (x.x)	MSC Priority (x.x)	HQ Priority (x.x)	Budget Request (\$1,000's)	Cumulative Budget Request	Total Estim Cost
BALDHILL	CEMVP	Stability (Static)	Unstable DS Spillway	8.1			\$0.	\$0.	\$0.
BALDHILL	CEMVP	Hydrologic	Emergency Spillway	8.2			\$0.	\$0.	\$0.
BALDHILL									
EAU GALLE									
EAU GALLE									
HIGHWAY 75 D									
HOMME DAM									
HOMME DAM									

of Dams w/ Deficiencies

Total # of Deficiencies

Show Top

All

Add New Deficiency

Sort Rows

ReSort

Modify Selected Field Value

Fill in Gaps

Comment

Delete Selected Deficiency

Print Selected Deficiency

Print All Deficiencies

Export to Excel

Exit


Screen 4.5

- Deficiencies Spreadsheet includes information regarding:**
 - Project/Dam Name
 - Project Identification Code
 - Date Found
 - Date Corrected
 - Deficiency #
 - Inspection Item
 - Short Title
 - Organization, Agency, or State
 - Dam Safety Issue?
 - Date Coordinated w/Ops & Budget
 - Funding Priorities
 - Work Category Code
 - Estimated Cost (\$1,000's)
 - Inspection Type
 - Category
 - Description
 - Repeating Deficiency?
 - Correction
 - Additional Evaluation Required?
 - Comment

Specifically, the Deficiencies Spreadsheet is used for:

- Documenting the specific remediation needs within the district, plans for studies, and remediation accomplishments
- Supporting the performance measure spreadsheet in generating the biennial report to FEMA
 - Remediation Needs and Accomplishments
- Providing budgeting guidance from the Districts to Division on prioritization of deficiencies and developing a remediation plan.
- Reviewing budgeting guidance from the Districts at the Division level, establishing a Division ranking for all deficiencies within the Division and communicating that ranking to Headquarters and back to the Districts.

The Documentation Spreadsheet



Documentation Details

Dam: HOMME DAM

Click on a cell to select it. Type into the cell to change the value. Double-click on a cell to cycle through possible values.

Documentation	Required?	Prepared?	Publication Date	Most Recent Update	Executive
Operations & Maintenance Manual	Yes	No			Click for Details
Water Control Manual	Yes	Yes	DECEMBER 1955	JULY 1981	Click for Details
As-Built Drawings	Yes	Yes	1949	NOVEMBER 1999	Click for Details
Periodic Inspection Reports	Yes	Yes	NOVEMBER 1971	JULY 2003	Click for Details
Emergency Action Plan	Yes	Yes	AUGUST 1989	FEBRUARY 1999	Click for Details
Flood Emergency Plan	Yes	Yes	AUGUST 1989	FEBRUARY 1999	Click for Details
Evacuation Plan	Yes	No	N/A		Click for Details
Project Geotechnical and Concrete Materials					Click for Details
Annual Instrumentation Evaluation Report					Click for Details
Foundation Report					Click for Details
Embankment Criteria & Performance Report					Click for Details

Done

Executive Summary

Comment Update



Screen 4.75

- Documentation Spreadsheet includes information regarding:
 - Documentation Category
 - Is the Document Required?
 - Has it been prepared?
 - When was it originally published?
 - When was it most recently updated?
 - Executive summary details

Specifically, the Documentation Spreadsheet can be used for:



- Supporting generation of the biennial report to FEMA
 - Emergency Action Planning Performance
- Providing executive summaries of periodic inspection reports, and other reports, to the Division.

Examples of Performance Measure Outputs within USACE




Number of Dams, (by District) (617 Total)


of Dams by Owner




Dam Safety Staff Size (By District)




- Total persons contributing to dam safety program (733 persons)



Dam Safety Staff (by Specialty)





- The data indicates that the dam safety staff consists primarily of Geotechnical, H&H and Structural engineers.




Dams in Need of Remediation


Owners of Dams in Need of Remediation, # of Dams




Identified Deficiencies



- Identified deficiencies primarily consist of deteriorated or damaged structures, and hydrologic deficiencies. Of significance, seepage and piping and static stability is identified, or is identified for future study, for 50 or more structures.



DSPMT Components



◆ **Dam Safety Program Performance Measures (DSPPM)**



◆ **National Inventory of Dams (NID)
Electronic Submittal Workflow**



◆ **Reporting Capabilities to National Oversight Organizations**




DSPMT


What is the NID Electronic Submittal Workflow?

“A natural extension of the NID and the Dam Safety Program Management Tools (DSPMT) to help users provide a consistent, error-checked electronic submittal of inventory information.”



NID Electronic Submittal Workflow





Applying the NID Inclusion Rules


Dams Meeting Search Criteria

Dam Name (1042 Dams)	River	Hazard	Dam Height	NID Height	Struct. Height	Hyd. Height	NID Storage	Max. SI
			0	0	0	0	0	
PORTER DAM	JOY CREEK		0	0	0	0	5	
1,2,3,4	ONION CREEK		0	0	0	0	182	
2-B FARM AND RANCH DAM	OFF CH-TR-OSO CREEK	LOW	5	5	5	5	5	
3M DETENTION POND	NONE	LOW	5.9	5.9	0	0	0	
ABERCROMBIE LEVEE	OFF CH-GUADALUPE RIVER	LOW	8	8	8	8	11	
AIC LAKE	PEDERNALES RIVER		0	0	0	0	36	
AINSWORTH DAM	DEEP CREEK		0	0	0	0	18	
AKERS DAM	MIDDLE COPPERA S CREEK		0	0	0	0	10	
ALLEN RESERVOIR	HORDS CREEK	LOW	0	0	0	0	5	
		LOW	0	0	0	0	22.5	
			0	0	0	0	80	
			0	0	0	0	24	
			0	0	0	0	12	
			0	0	0	0	12.5	
			0	0	0	0	130	
		LOW	11.1	11.1	0	0	49	
			0	0	0	0	10	
			0	9	9	0	1	
			0	0	0	0	1	
			15	15	15	15	28	
			18	18	18	18	48.6	
			14	14	14	14	17	
			17	17	17	17	41	
			17	17	17	17	41	

Review DSPPM **Modify Selected** **Modify ALL** **Sort Rows** ☐ Min->Max ☐ Max->Min

Comment **Show Details** **Print Summary** **Delete Selected** **Exit/ Return to Search Criteria** **?** Screen 58

- NID Inclusion is based strictly on Hazard Potential, NID Height, and NID Storage.
- For each record, the value which caused the dam to be excluded is shown in RED.




Quality Assurance Tools Interface

NID Submittal Quality Assurance Tools

Define Synonyms Set Coded Fields	Show the Candidate NID Submittal
Show Candidate NID Submittal Dams which do not have an NID ID Assigned	Special NID Comparison Functions Requiring a Password
Show Dams with Duplicate NID Identification Numbers	Password for Access to NID Data: <input type="text"/>
Identify/Delete Potential Duplicate Submittal Data	Show Differences Between the Candidate Submittal and the Current NID
Histograms/ Search Capability	Show Dams which are in the NID but are NOT in the Candidate Submittal
Re-Import a Field from the State/Federal Agency Local Inventory Database Overwriting an Existing Field in the NID Submittal	Show New Dams in the Candidate Submittal NOT in the Current NID
Convert State Regulated Dam Field to "Y" if the Current Value is Non-Zero or to "N" if the Current Value is Zero or Blank	Convert Last Inspection Date to MM/DD/YYYY
	Globally Populate a Selected NID Candidate Field with a Specified Value

Comment Exit ? Screen 81

DSPMT Components



◆ **Dam Safety Program Performance Measures (DSPPM)**



◆ **National Inventory of Dams (NID) Electronic Submittal Workflow**



◆ **Reporting Capabilities to National Oversight Organizations**



DSPMT



Why are Reporting Capabilities Needed to National Oversight Organizations?

“Facilitating the development, documentation, and modification of practices by supporting performance measures which directly address all aspects of an organizations dam safety program.”


What National Data Collection Efforts have Utilized the DSPMT?

- 2002 NID Update
- 2003 NDSRB State Evaluation Criteria Reports (2002 Reporting Year)
- 2004 NDSRB State Evaluation Criteria Reports (2003 Reporting Year)
- 2005 Combined NDSRB/ASDSO Questions (State Evaluation Criteria Report + ASDSO Annual Survey), (2004 Reporting Year)
- 2004 Update of State Regulated Dam Field in the 2002 NID
- 2004 Update of USACE Dam Safety Deficiencies and Budgeting Priorities for FY06
- 2005 Generation of the draft USACE Biennial Report to FEMA (Reporting Years 2004-2005) (Data collection effort completed)
- 2005 NID Update (effort underway)


NID Electronic Submittal Status (9/16/2002)



State Participation in the 2003, 2004 NDSRB State Evaluation Criteria Report




2003



2004


- Green indicates that the State provided the NDSRB data.

Sample Timeline Data from NDSRB Report



- Total Number of State Regulated Dams


Sample Timeline Data from NDSRB Report



- Total Number of Inspections

Sample Timeline Data from NDSRB Report

EAP Completion Percentage for High Hazard Potential Dams



- EAP Completion % for High Hazard Potential Classification Dams

A map of the United States where several states are highlighted in green. The green states include Washington, Oregon, California, Nevada, Idaho, Utah, Arizona, New Mexico, Texas, Oklahoma, Kansas, Nebraska, South Dakota, North Dakota, Minnesota, Iowa, Missouri, Arkansas, Louisiana, Mississippi, Alabama, Georgia, Florida, South Carolina, North Carolina, Virginia, West Virginia, Kentucky, Tennessee, Indiana, Michigan, Ohio, Pennsylvania, Delaware, Maryland, Connecticut, Rhode Island, Massachusetts, Vermont, New Hampshire, Maine, Alaska, and Hawaii. All other states are colored white.

- 38

USACE District/Division Participation in Providing Inputs for the Biennial Report to FEMA in 2005

Divisions

Districts

- Green indicates that the Organization provided DSPMT-format electronic submittal data


39

- # USACE District/Division Participation in Providing Inputs for the Biennial Report to FEMA in 2005
-
- The image contains two maps of the United States, each divided into USACE Districts and Divisions. The left map is labeled 'Districts' and the right map is labeled 'Divisions'. Green shading indicates participation in providing DSPMT-format electronic submittal data.
- Districts (Left Map):**
- SPN
 - IWS
 - IWP
 - IWW
 - IWO
 - MVP
 - LRE
 - LRC
 - MVR
 - LRH
 - NAO
 - SAW
 - SAC
 - SAS
 - SAM
 - SAJ
 - MVM
 - MVH
 - SWG
 - SWF
 - SWT
 - SPA
 - SPL
 - SPK
 - POA
- Divisions (Right Map):**
- NWD
 - SPD
 - SWD
 - MVD
 - SAD
 - LRD
 - NAD
- Green indicates that the Organization provided DSPMT-format electronic submittal data


Where is this going?

- Continued Utilization of DSPMT for Updating the NID
 - Short Term Goal: Annually
 - Longer Term Goal: In Near-Real Time
- Continued Utilization of DSPMT for USACE biennial reporting to FEMA
- Utilization of DSPMT for tracking SPRA within USACE
- Continued Utilization of DSPMT for Combined NDSRB/ASDSO reporting of State Program Performance data
- Incorporation of CRS questions into combined NDSRB/ASDSO/CRS annual reporting starting in 2006

DSPMT Information Flow



Please Stop by the USACE TEC Exhibit booth for a Demonstration



- For help installing or utilizing the software contact Mike Grounds
Phone: (256) 771-0014
e-mail: mike@riversrus.com





US Army Corps
of Engineers
Sacramento District

SUCCESS DAM SEISMIC REMEDIATION



Success Dam and Reservoir



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Introduction


■ Overview

- Seismic Problem at Success Dam
- Recent Milestones
- Risk Analysis and Operating Restriction
- Alternative Selection
- Current Status
- Success Spillway Enlargement
- Challenges



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project Location Map





US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project Key Key Facts

- Dual Purpose Reservoir – Flood Control & Irrigation
- Completed in 1961
- Original Cost \$14.1M
- 185 ft high X 3,450 ft long
- Earth-filled dam
- Storage capacity = 82,300 acre-ft
- Provides 47-year flood protection to the city of Porterville and 200,000 acres downstream





US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Primary Earthquake Sources


- Active Faults within 100-mile radius
 - Premier Fault – 13 miles (M 6.75) MCE *
 - San Andreas – 72 miles (M 8.0) OBE **
 - Owens Valley – 52 miles (M 7.6)
 - White Wolf – 57 miles (M7.5)
- *Maximum Credible Earthquake – worst predicted earthquake
(max ground acceleration = 0.28g)
- **Operating Basis Earthquake – expected during life of project
(max ground acceleration= 0.1g)



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Primary Seismic Sources






US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Historic Earthquakes






US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Cross –Section of Dam




Most of the problem materials are the stream deposits known as “Recent Alluvium”



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Recent Alluvium






US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Dam failure at early stages of MCE

Maximum Credible Earthquake

Upstream
slumping





US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Milestones

- 1999 – Corps completes DSAP Evaluation Report
- 2000 – Construction General Funds appropriated
- 2000-2003 - Further studies and modeling indicate Recent Alluvium will liquefy.
- 2003-2004 - Risk assessment performed
- Sep 2004 – Selection of Roller Compacted Concrete as preferred remediation alternative
- Nov 2004 – CE-SPK Dam Safety Committee recommends temporary operating elevation restriction of 620' or approximately 1/3 capacity
- Nov 2004 – RCC analysis and studies begin



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Risk Analysis and Operating Restriction

■ Risk Analysis Results

- Risk of uncontrolled release of the reservoir: 1/285 per year. Required 1/10,000
- Short-term risk reduction: Elevation 620'
 - Eliminates overtopping
 - Reduces seepage failure risk to 1/950
 - Reduces loss of life to within acceptable guidelines
 - May only be in effect for 7 years.
- Long-term risk reduction requires remediation of dam



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Risk Analysis and Operating Restriction

■ Effects of reservoir restriction

- Loss of Recreation -
\$2.8M/year (average)
- Flooding in Tulare Lakebed (wet years = 20%) -
\$.06M/year (average) - Range \$0 - \$3.2M
- Loss of Storage (Agricultural water users) -
\$1.4M/year (average) - Range \$0 - \$3.0M



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project Alternative Selection



IN-SITU ALTERNATIVE



OVERLAY ALTERNATIVE



**ROLLER COMPACTED CONCRETE
ALTERNATIVE**



**NEW EARTHEN EMBANKMENT
ALTERNATIVE**



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Current Status

- **RCC Design and Engineering**
 - Foundation exploration -75% complete
 - Structural Analysis - 30% complete
 - Environmental Impact Study (EIS) started
 - Quarry Sites – initial testing begun
 - Tower and Conduit analysis started
 - Real Estate Plan started



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Ongoing and Future Contracts

- Sonic drilling for continuous core sample
- 100' Shaft design and construction
- Concrete coring of inlet tower for seismic analysis
- Initial excavation of quarry site – 200 ton
- Geophysics testing to profile foundation
- Shear wave testing
- Panel of consultants review of RCC decision
- Rock screening and crushing
- Sample existing embankment for materials



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project Spillway Enlargement Project





US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project

Spillway Enlargement Project

- PCA signed June 2003
- Non-Federal Sponsors
 - Lower Tule River Irrigation District
 - The Reclamation Board, State of CA
- Estimated cost \$28M
- Dual Purpose Project
 - Increase Flood Control from 1:47 to 1:100
 - Increase storage capacity by 29,000 ac-ft
- Work stopped pending further progress on seismic remediation of Success Dam



US Army Corps
of Engineers
Sacramento District

Success Seismic Remediation Project Challenges

- Roller Compacted Concrete Dam
 - Foundation materials inconsistent
 - Cement availability and price stability
- Real Estate Acquisition
 - Real Estate Plan dependent upon EIS
 - Costs of mobile home park relocations
 - Purchase 40-acre parcel before EIS
- Funding
 - Large FY07 and FY08 funding requirements




US Army Corps
of Engineers
Sacramento District

SUCCESS DAM

Questions



Little Rock District



Clearwater Dam Major Rehab Project

Bobby Van Cleave, P.E.

Geotechnical & Civil Section - Design Branch

Little Rock District Corps of Engineers

✉ E-Mail bobby.e.vancleave@swl02.usace.army.mil


☎ TEL (501) 324-5055 Ext. 1420

☎ FAX (501) 324-5265

Clearwater Lake

Vicinity Map

1 inch equals 40 miles



Legend

- state boundary
- county boundary
- project boundary



CLEARWATER LAKE - MISSOURI





Little Rock District

What's the problem(s)?



Little Rock District

Significant Deficiencies

- Long-Term Seepage
 - Seepage has been observed at and around the downstream left abutment since first filling.
 - Several remediation attempts have been accomplished over the past 60 years.
 - A sinkhole appeared on the upstream face of the embankment in 2003.
- Seismic
 - Clearwater is located in the New Madrid Seismic Zone.
 - Some of the alluvial soils beneath the structure may be susceptible to liquefaction under certain earthquake events.
- Spillway
 - There is currently material located within the spillway that should be removed to allow for the PMF event.



Little Rock District

What can happen?



Little Rock District

Consequences

- In the event of a dam breach caused by seepage or seismic
 - Total damages: \$168,520,000
 - Total loss of life: 340



Little Rock District

When were seepage
problems first observed?

Original Construction – STA 41+68



Looking E from 150' U.S. of station 41 + 68: General view of cut-off trench operations.

Original Construction – STA 39+20




Looking S from 175' US of station 39 / 20: Open joint in cut-off trench foundation.

Original Construction – STA 40+15





Looking NW from 35' U.S. of station 40 / 15: Open joint in cut-off trench foundation.

ORIGINAL DESIGN



EXISTING STRUCTURE



Top of dam elevation 608
Top of parapet wall 611
Pool elevation 494


← Upstream

Centerline
of Dam

Impervious
Blanket

Toe of
Dam

Seepage
Berm





Little Rock District

CLEARWATER DAM POOL OF RECORD – MAY 2002 ELEVATION 566.7





Little Rock District

POOL OF RECORD – MAY 2002

LOOKING TOWARDS LEFT ABUTMENT






Little Rock District

POOL OF RECORD – MAY 2002 EMERGENCY SPILLWAY LOOKING TOWARDS NORTHEAST



CLEARWATER DAM DISCHARGE IMPACTS



Black River Stage @ Popular Bluff, MO (ft.)


Clearwater Dam – Sinkhole Investigation

15 January 2003



Legend

● sinkhole



Clearwater Dam – Sinkhole Investigation

16 January 2003



Clearwater Dam – Sinkhole Investigation

16 January 2003



Final excavation at 25 feet deep





Little Rock District

Geophysical and Subsurface Investigations



Little Rock District

- Kansas Geological Survey – surface wave, reflection
- Sonic Drilling – 6 borings, 50' into rock
- Bureau of Reclamation – crosshole tomography
- ERDC – SP, EM conductivity, ER

KANSAS GEOLOGICAL SURVEY



KANSAS GEOLOGICAL SURVEY



Sonic drilling – Clearwater Dam – 8 April 2003





1' of concrete below impervious core

Sinkhole boring SH-1A

9 April 2003

Bureau of Reclamation – June 2003






Little Rock District

What information was
gained from these
investigations?



PLAN VIEW OF CORE TRENCH



CROSS-SECTION OF CORE TRENCH



Little Rock District

MAJOR REHAB PROJECT SUMMARY

- PDT arrived at two primary structural alternatives (out of 10 measures evaluated) that address the Clearwater seepage problems.
- Report submitted June 04.
- Approved by SWD 6 August 04.
- Receive CG Wedge Funds from HQ 13 Aug 04.



Little Rock District

MAJOR REHAB PROJECT SUMMARY

- Design/Const schedule developed Oct 04
- New survey initiated in Oct 04, complete Feb 05
- Seepage consultants on board Feb 05
 - Bruce, Silva, Poulos
- Cutoff wall through the centerline of the dam was approved. Wall location has been moved to centerline of clay core by SWL and Consultants with approval by SWD and HQ.



Little Rock District

What immediate
remediation efforts need to
be performed?



Little Rock District

Foundation Drilling and Grouting – Sinkhole Repair Project




Location of Sinkhole and Grouting Project



Little Rock District

Clearwater Dam

Embankment Cross Section




Clearwater Dam – Sonic Drilling



Clearwater Dam – Grout Line





IntelliGrout™
The Science of Grouting


CLEARWATER DAM SINKHOLE REPAIR
PIEDMONT, MISSOURI
FOUNDATION DRILLING AND GROUTING
CONTRACT NO.: W9127S-04-C-0003



US Army Corps of Engineers
Civil Works Division

FIGURE 3
PROFILE VIEW OF LMG HOLES
Updated as of 3-15-05

LOW MOBILITY GROUT HOLES – PLAN VIEW





Little Rock District

FY 04-05 Grouting Contract Summary

- November 2003 – ACT/Gannett-Fleming
- December 2003 – NTP
- April 2004 – grouting began in rock
- August 2004 – grouting 75% complete; discovery of unknown cavity
- November 2004 – modify contract for low mobility grout (LMG)
- April 2005 – complete LMG
- May 2005 – contractor demob



Little Rock District

Will seismic issues affect
seepage remediation?



Little Rock District

SEISMIC STUDY EFFORTS

- Hired FMSSM to perform parametric seismic analysis.
- Obtained services of seismic consultants – Seed, Castro, Lorig, Hempen.
- Performed additional SPT for limited seismic investigation requested by consultants to verify historical drilling data.

Drilling and Sampling Photos



Instrumented Drill Rod to Measure Hammer Energy

Drilling and Sampling Photos



SPT Analyzer Readout Terminal

Drilling and Sampling Photos




Disturbed Tube Sample



Little Rock District

Pseudostatic Analyses with UTEXAS4

NO.	DESCRIPTION	UNIT WEIGHT	SHEAR STRENGTH	PORE PRESSURE
1	Alluvium - Sand & Gravel	132	Cohesion: 0 Friction angle: 27	Piezometric Line no. 1
2	Alluvium - Sand & Clay	125	Cohesion: 480 Friction angle: 15	Piezometric Line no. 1
3	Impervious Core	125	Cohesion: 640 Friction angle: 10	Piezometric Line no. 1
4	Stone Protection	135	Cohesion: 0 Friction angle: 42	Piezometric Line no. 1
5	Pervious Shell	130	Cohesion: 0 Friction angle: 34	Piezometric Line no. 1
6	Seepage Blanket	115	Cohesion: 240 Friction angle: 8	Piezometric Line no. 1
7	Upstream Berm	122	Cohesion: 480 Friction angle: 10	Piezometric Line no. 1
8	Limestone Rock	160	Very Strong	Not Applicable





Little Rock District

SEISMIC STUDY SUMMARY

- Slope stability and FLAC analyses indicate no slope failure under current OBE assigned by ERDC.
- SPT samples were relatively consistent with historical data.
- The cutoff wall should incorporate a plastic concrete to match the strengths of the embankment materials.
- FMSM to finalize data and report in July.
- Continue seismic analysis through DSAP (FY06-FY08).



Little Rock District

MAJOR REHAB PROJECT STATUS

- Phase I –exploratory drilling/grouting along full length of dam. (early FY06)
- Phase II – construction of work platform, Cutoff wall construction and seepage blanket extension. (late FY06)

CUTOFF WALL PROJECT

PROPOSED CUTOFF WALL

- DEPTH INTO ROCK: 60 FT+/-
- TOTAL DEPTH: 200 FT+/-
- LENGTH: 4,300 FT+/-

SEEPAGE BLANKET EXTENSION

EL 611.0 TOP WALL

EL 608

EL 575

EL 567 POOL OF RECORD

IMP. BERM

CORE

SHELL

EL 500

EL 470

ALLUVIAL

EL 435

GROUT LINES

ORIGINAL GROUT CURTAIN

BEDROCK

RIVER

DRAWING NOT TO SCALE

DRAWING NOT TO SCALE



Little Rock District

CRITICAL INFORMATION NEEDED FOR CUTOFF WALL DESIGN

- Depth of rock embedment.
- Permeability of existing soils and rock.
- Method of construction:
 - Rock mill or Secant pile
- The presence of any other large cavities/features.



Little Rock District

MAJOR REHAB AND DAM SAFETY PROJECT FUNDING

- FY05
 - **\$1.05M CG**– detailed design for MRP
 - Per direction from HQ/SWD, utilized \$350k for limited seismic deformation and stability analysis
- FY06
 - **\$22M CG** – Phase I construction (exploratory drilling/grouting)
 - Complete design and initiate Phase II construction (work platform, cutoff wall)
 - **\$245k O&M** – Seismic Intensity for MCE, Borings and Testing
- FY07
 - **\$23M CG** – Phase II construction (work platform, cutoff wall)
 - **\$260k O&M** – Seismic Analysis Phase I and II




Little Rock District


MAJOR REHAB AND DAM SAFETY PROJECT FUNDING

- FY08
 - \$23M CG – Phase II construction (cutoff wall)
 - \$300k O&M – Seismic Evaluation Report
- FY09
 - \$21.1M CG – Phase II construction (cutoff wall)
- FY10
 - \$23M CG – Phase II construction (work platform, cutoff wall)

Little Rock



District



*US Army Corps of
Engineers,
Nashville District*

Wolf Creek Dam Seepage Major Rehabilitation Evaluation




Outline of Topics

- **Project Features**
- **Foundation Problems**
- **1960's Distress Indicators and Actions**
- **Post Wall Performance/Current Distress Indicators**
- **Proposed Remedy**



Project Location






Project Features






EMBANKMENT SECTION STA. 44+50L






EMBANKMENT PLAN





Geology





Foundation Treatment Problems

- Treatment techniques inadequate for this geology
- Most of the alluvium left in place
- Except for cut-off trench, no embankment foundation treatment
- Cutoff trench design and construction inadequate

1-A, -B, and -C. The bottom of this section of trench, at this stage of excavation, is still in overburden except for a few narrow areas where the rock salients showing in the overburden slopes were connected across the trench line. It is proposed to excavate the floor of the trench to continuous sound rock for the grout curtain. • Overhangs and loose rock



8-25-42. Looking SE in trench from
sta. 5+50.


I-E

will be removed only where they cross the line of the trench, since the earthfill in the sides of the trench will have the function only of stability and not of an absolutely uniform tight contact with the trench walls. Tamping will supplement the regular rolling of the fill as required under the overhangs and irregular salients. •



8-22-42/looking S in trench from vicinity embankment sta. 36+10. I-6

I-6. Note rock channel between points ω and V , with abrupt ledge floor at level of V . This floor was underlain by solution weathered rock and was not continuous (see photo I-H). Above the floor, the walls were extremely irregular, with overhanging ledges. These were knocked off and weathered rock removed to condition shown in photo I-F.



9-21-42/looking S in trench from vicinity embankment sta. 36+10. I-6

I-6. Note final condition of rock channel between points ω and V (see photo I-6). This channel is along line 3A of Exhibit 3. Note tapering continuation of the channel across intersecting channel.

Before

After



4-2-42. looking SE along
hole at trench sta. 27+95. **IV-A**



4-2-42. looking E across
hole at trench sta. 27+95. **IV-B**


IV-A and -B. The hole is a solution widened joint, crossing the trench at right angles. Note differential solution and resulting overhangs in rock faces. These re-entrants were apparently well filled with silt.



31,822

19 November 1942

View of backfilling operations in cavity at
Sta. 50+00 on cutoff trench




Cave

Cave

Solution Features

**Looking from
monolith 36 into
cutoff trench
where it ties
into monolith 37**

Cave



End Monolith (37)






61/421

14 August 1947


Filling core trench, Mon. 37



Caves

**Terminus of
cutoff trench**

**Founding Elevation
Monolith 37**



Monolith 37

U/S

**Pushing Soil
into Cave**


**Right Face of
Monolith**

D/S Face

Embankment




Initial Distress Indicators 1960's







1968 Sinkhole






Piping and Sinkhole Development






1960's and 70's Remedial Features






Profile along Diaphragm Wall





Diaphragm Wall



Typical Section




Post Wall Performance/Current Distress Indicators

- Piezometers
- Wet Areas
- Settlement
- Soft Zones
- Temperature Survey
- Other




High PZ Pressures







Post Wall Performance – Wet Areas



Overall View
Wolf Creek Dam




Post Wall Performance - Settlement




LEGEND

- OBSERVED SETTLEMENT
- PREDICTED SETTLEMENT





2002-2003 Resonant Sonic Investigations





Other Concerns/Distress Indicators

- **Cool Spots from Piezometer Temp. Survey**
- **Cable Tunnel Seepage and Cracking**
- **Increased Seepage and Instability Problems in the D/S Riverbank**
- **Structural Integrity of Existing Wall**





Reasons for Continuing Distress

- Seepage coming around ends of wall
 - Through features untreated beneath monoliths
 - Around right end where no wall exists
- Below wall through features untreated or partially treated by previous grouting
- Through defects in wall itself




Proposed Remedy






Proposed Secant Wall





Unconstrained Construction Cost By FY






Reliability Analysis

Hazard Rates

Summary of Hazard Rates for Wolf Creek Dam





Questions?





Speaker Info. Slide

- **Michael F. Zoccola P.E.**
- **Nashville District Corps of Engineers**
- **615-736-5693**
- **michael.f.zoccola@lrn02.usace.army.mil**